PROJECT MANUAL

JOSEPH BONNHEIM ES
TELECENTER UPGRADE

PROJECT/CONTRACT NUMBER: 0183-464

SACRAMENTO CITY
UNIFIED SCHOOL DISTRICT

June 29, 2023

17. The District

DOCUMENT 00 21 13

INSTRUCTIONS TO BIDDERS

Bidders shall follow the instructions in this document, and shall submit all documents, forms, and information required for consideration of a bid.

Sacramento City Unified School District ("District") will evaluate information submitted by the apparent low Bidder and, if incomplete or unsatisfactory to District, Bidder's bid may be rejected at the sole discretion of District.

1. Bids are requested for a general construction contract, or work described in general, for the following project ("Project" or "Contract"):

   Joseph Bonnheim ES Telecenter Upgrade
   Project Number #0 183-464

2. A Bidder and its subcontractors must possess the appropriate State of California contractors' license and must maintain the license throughout the duration of the project. Bidders must also be registered as a public works contractor with the Department of Industrial Relations pursuant to the Labor Code. Bids submitted by a contractor who is not properly licensed or registered shall be deemed nonresponsive and will not be considered.

3. Bidders are advised that on the date that bids are opened, the District Offices will not be open to bidders. Bids will be opened privately due to electronic submission through eBuilder. Bid Documents and at www.scusd.edu/construction - projects - bids . The District reserves the right to verify the genuineness of any bid security.

4. Bidders must submit bids on the documents titled Bid Form and Proposal, and must submit all other required District forms. Bids not submitted on the District's required forms shall be deemed nonresponsive and shall not be considered. Additional sheets required to fully respond to requested information are permissible.

5. Bidders shall not modify the Bid Form and Proposal or qualify their bids. Bidders shall not submit to the District a re - formatted, re - typed, altered, modified, or otherwise recreated version of the Bid Form and Proposal or other District - provided document.

6. Bids shall be clearly written and without erasure or deletions. District reserves the right to reject any bid containing erasures, deletions, or illegible contents.

7. Bidders must supply all information required by each Bid Document. Bids must be

27. Time for Completion: District may issue a Notice to Proceed within NINETY (90) days from the date of the Notice of Intent to Award. Once Contractor has received the Notice to Proceed, Contractor shall complete the Work within

30. Prior to the award of Contract, District reserves the right to consider the responsibility of the Bidder. District may conduct investigations as District deems necessary to assist in the evaluation of any bid and to establish the responsibility, including, without limitation, qualifications and financial ability of Bidders, proposed subcontractors, suppliers, and other persons and organizations to perform and furnish the Work in accordance with the Contract Documents

DOCUMENT 00 31 19

b. District does not warrant, and makes no representation regarding, the accuracy or thoroughness of any information regarding existing conditions. Bidder represents and agrees that in submitting a bid it is not relying on any information regarding existing condition s supplied by District.

c. Under no circumstances shall District be deemed to warrant or represent existing above - ground conditions, as - built conditions, or other actual conditions, verifiable by independent investigation. These conditions are verifiable by Bidder by the performance of its own independent investigation that Bidder must perform as a condition to bidding and Bidder should not and shall not rely on this information or any other information supplied by District regarding existing conditions.

d. Any information shown or indicated in the reports and other data supplied herein with respect to existing underground facilities at or contiguous to the Project may be based upon information and data furnished to District by the District's employees and/or

8. Receipt and acceptance of the fe

In the event suit is brought upon this bond, the Surety will pay for all reasonable expenses and attorney's fees incurred by the Owner in such suit, in addition to the penal sum of this bond.

DOCUMENT 00 43 36

DESIGNATED SUBCONTRACTORS LIST
(Public Contact Code Sections 4100- 4114)

PROJECT: Joseph Bonnheim ES T elecenter Upgrades 0183-464

Bidder acknowledges and agrees that it must clearly set forth below the name, location and California contractor license number of each subcontractor who will perform work or labor or render service to the Bidder in or about the construction of the Work or who will specially fabricate and install a portion of the Work according to detailed drawings contained in the plans and specifications in an amount in excess of one -half of one perce nt (0.5%) of Bidder's total Base Bid and the kind of Work that each will perform. Vendors or suppliers of materials only do not need to be listed.

Bidder acknowledges and agrees that, if Bidder fails to list as to any portion of Work, or if Bidder lists more than one subcontractor to perform the same portion of Work, Bidder must perform that portion itself or be subjected to penalty under applicable law. In case more than one subcontractor is named for the same gper upecte ( )06tts7w 0.325 0 Td [(th)-1.5 (e)]TJ 0 Tc 6 u3 Tc 0.000
Tw 0 Tc (,)jTc 0 Tw (rk)-15.4

DOCUMENT 00 45 26

WORKERS' COMPENSATION CERTIFICATION

PROJECT/CONTRACT NO Josep

DOCUMENT 00 45 46.01

PREVAILING WAGE AND RELATED LABOR REQUIREMENTS CERTIFICATION

PROJECT/CONTRACT NO.: Joseph Bonnheim ES Telecenter Upgrades 0183-464
between the Sacramento City Unified School District ("District") and _____
_____("Contractor" or "Bidder") ("Contract" or "Project").

I hereby certify that I will conform to the State of California Public Works Contract requirements regarding prevailing wages, benefits, on -site audits with 48 -hours' notice, payroll records, and apprentice and trainee employment requirements, for all Work on the above Project including, without limitation, labor compliance monitoring and enforcement

DOCUMENT 00 45 46.02

DRUG -FREE WORKPLACE CERTIFICATION

PROJECT/CONTRACT NO: Joseph Bonnheim ES Telecenter Upgrades 0183-464
between the Sacramento City Unified Sd576 14J 0 (3.7 (d)-14.9 (e)-1.6 (s)]TJ 0 Tc 0 Tw 101 Tw0101 Tw0101 l Tc 0.004

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter

DOCUMENT 00 45 46.03

TOBACCO -FREE ENVIRONMENT CERTIFICATION

PROJECT/CONTRACT NO.: Joseph Bonnheim ES Telecenter Upgrades 0183-464
between the Sacramento City Unified School District ("District") and _____
_____("Contractor" or "Bidder") ("Contract" or "Project").

This Tobacco-Free Environment Certification form is required from the successful Bidder.

Pursuant

DOCUMENT 00 45 46.07

IMPORTED MATERIALS CERTIFICATION

PROJECT/CONTRACT NO.: Joseph Bonnheim Telecenter Upgrades 0183-464 between the Sacramento City Unified School District ("District") and _____ ("Contractor" or "Bidder") ("Contract" or "Project").

This form shall be executed by all entities that, in any way, provide or deliver and/or supply any soils, aggregate, or related materials ("Fill") to the Project Site and shall be provided to

DOCUMENT 00 45 49

REGISTERED SUBCONTRACTORS LIST
(Labor Code Section 1771.1)

PROJECT: Joseph Bonnheim ES T elecenter Upgrades 0183-464

Date Submitted (for Updates): _____

6 (a-116 (C)-10.9 (o0 Td [(L)-8 625.1J 058 (s06531.289f Tt B206J 0 T4 Tc -b.0065Twor)0.o0.5 56.1i6 -116 (C)-10.9 (o0 T

Subcontrac (r) ET EMC BT /H2 <<<<<<<0 0 9 9oTw 9.96 0 0 9.96 60 69.84 Tm ( )Tj ET EMC 4.5 9 0 9BT 0 Tc 0 Tw 9 0 262

DOCUMENT 00 45 90

POST BID INTERVIEW

PART 1 – GENERAL

1.01 SUMMARY

If requested by the District, this Section requires the apparent low bidder to attend and participate in a Post Bid Interview with the Construction Manager, prior to award of any contract by the District. The Post Bid Interview will be scheduled by the Construction Manager within three (3) calendar days after the date of bid.

1.02 REQUIRED ATTENDANCE

A. A duly authorized representative of the apparent low bidder is required to attend the Post Bid Interview, in person.

B. The apparent low bidder's authorized representative(s) must have (1) knowledge of how the bid submitted was prepared, (2) the person responsible for supervising performance of the su,8.6 (h)-22.6 (c)-2.1 (e)0.7 ( )d8.5 (e)0.6 (rf0 Tc-8.6 (3TJ 0.00( ).5 8h)-

(10) Project Schedule and Schedule Requirements

(11) Critical Dates Requirement for Other Bid Packages

(12) Prevailing Wage Requirements

(13) Liquidated Damages

(14) Required Documentation for Contract Administration

(15) Contract Coordination Requirements

1.04 POST BID INTERVIEW DOCUMENTATION

The Construction Manager will document the Post Bid Interview on the form attached to this Section. Both the apparent low bidder and the Construction Manager are required to sign

POST BID INTERVIEW

CONSTRUCTION MANAGER

[Name]
[Address 1]
[Address 2]

(3) Will there be a gap between the per occurrence amount of any underlying policy and the start of the coverage under the Umbrella or Excess Liability Insurance Policy?

W-10 (T)-15 (2(l)-373 0 Td ( )T

DOCUMENT 00 52 13

AGREEMENT

THIS AGREEMENT IS MADE AND ENTERED INTO THIS _____DAY OF _____ _____, 20___, by and between the Sacramento City Unified School District ("District") and _____("Contractor") ("Agreement").

WITNESSETH: That the parties hereto have mutually covenanted and agreed, and by these presents do covenant cot 0 Td ( )pTj t Seie3ren

4. Time for Completion : It is hereby understood and agreed that the Work under this Contract shall be completed within Two hundred and nine (209) consecutive calendar days ("Contract Time") from the date specified in the District's Notice to Proceed. This includes construction, punch list and project acceptance, and completion of closeout in coordination with the schedule provided at bid time.

5. Completion - Extension of Time : Should the Contractor fail to complete this Contract, and the Work provided herein, within the time fixed for compl etion, due allowance being made for the contingencies provided for herein, the Contractor shall become liable to the District for all loss and damage that the District may suffer on account thereof. The Contractor shall coordinate its Work with the Work of all other contractors. The District shall not be liable for delays resulting from Contractor's failure to coordinate its Work with other contractors in a manner that will allow timely completion of Contractor's Work. Contractor shall be liable for delays to other contractors caused by Contractor's failure to coordinate its Work with the Work of other contractors.

6. Liquidated Damages : Time is of the essence for all work under this Agreement. It is hereby understood and agreed that it is and will be difficul t and/or impossible to ascertain and determine the actual damage that the District will sustain in the event of and by reason of Contractor's delay; therefore, Contractor agrees that it shall pay to the District the sum of One T the tletontld 1.928 0 Td (t)-3.6 89

the actual original signature. All counterparts so executed shall constitute one Contract binding all the Parties hereto.

IN WITNESS WHEREOF, accepted and agreed on the date indicated above:

[CONTRACTOR NAME]	SACRAMENTO CITY UNIFIED SCHOOL DISTRICT
By: _____	By: Rose Ramos
Title: _____	Title: Chief Business & Operations Officer

NOTE: If the party executing this Contract is a corporation, a certified copy of the by-laws, or of the resolution of the Board of Directors, authorizing the officers of said corporation to execute the Contract and the bonds required thereby must be attached herere.7 (d)(p)0.5 (a)-9.5

information contained therein, against disclosure to the fullest extent permitted by law.

3. Format and Contents of Escrow Bid Documentation

a. Contractor may submit Escrow Bid Documentation in its usual cost-estimating format; a standard format is not required. The Escrow Bid Documentation shall be submitted in the language (e.g., English) of the specification.

b. Escrow Bid Documentation must clearly itemize the estimated costs of performing the work of each bid item contained in the bid schedule, separating bid items into sub-items as required to present a detailed cost estimate and allow a detailed cost review. The Escrow Bid Documentation shall include all subcontractor bids or quotes, supplier bids or quotes, quantity takeoffs, crews, equipment, calculations of rates of production and progress, copies of quotes from subcontractors and suppliers, and memoranda, narratives, add/deduct sheets, and all other information used by the Contractor to arrive at the pre lranClquo (ti)-11.1 .036 0 Td ( )Tj -.6 (a)2.6 ( )0.6 rm Es,thelrs da78 0 Te qur

Contractor may examine the Escrow Bid Documentation without that subcontractor present upon an additional THREE (3) calendar days' notice if a representative of that subcontractor does not appear at the time set.

c. The Escrow Bid Documentation will be returned to Contractor at such time as the Contract has been completed and final settlement has been achieved.

END OF DOCUMENT

4. Contractor shall be responsible for paying all fees for the expenses incurred by Escrow Agent in administering the Escrow Account, and all expenses of District. The District will charge Contractor $ _____ for each of District's deposits to the escrow account. These expenses and payment terms shall be determined by District, Contractor, and Escrow Agent.

5. Interest earned on securities or money market accounts held in escrow and all interest earned on that interest shall be for sole account of Contractor and shall be subject to withdrawal by Contractor at any time and from time to time without notice to District.

6. Contractor shall have the right to withdraw all or any part of the principal in the Escrow Account only by written notice to Escrow Agent accompanied by written authorization from District to Escrow Agent that District consents to withdrawal of amount sought to be withdrawn by Contractor.

7. District shall have the right to draw upon the securities and/or withdraw amounts from the Escrow Account in the event of default by Contractor. Upon seven (7) days' written notice to Escrow Agent from District of the default, if applicable, Escrow Agent shall immediately convert the securities to cash and shall distribute the cash as instructed by District. Escrow Agent shall not be authorized to determine the validity of any notice of default given by District pursuant to this paragraph, and shall promptly comply with District's instructions to pay over said escrowed assets. Escrow Agent further agrees to not interplead the escrowed assets in response to a conflicting demand.

8. Upon receipt of written notification from District certifying

10. Names of persons who are authorized to give written notice or to receive written notice on behalf of District and on behalf of Contractor in connection with the foregoing, and exemplars of their respective signatures are as follows:

On behalf of District: On behalf of Contractor:

Title Title

Name Name

Signature Signature

keep and perform the covenants, conditions, and agreements in the Contract and any alteration thereof made as therein provided, on its part to be kept and performed at the time and in the intent and meaning, including all contractual guarantees and warrantees of materials and workmanship, and shall indemnify and save harmless the District, its trustees, officers and agents, as therein

the Civil Code, so as to give a right of action to them or their assigns in any suit brought upon this bond.

Should the condition of this bond be fully performed, then this obligation shall become null and void; otherwise it shall be and remain in full force and affect.

And the Surety, for value received, hereby stipulates and agrees that no change, extension of time, alteration, or addition to the terms of Contract or the specifications accompanying

SACRAMENTO CITY USD
Joseph Bonnheim ES

DOCUMENT 00 63 63

The undersigned Contractor approves the foregoing as to the changes, if any, to the Contract Price specified for each item, and as to the extension of time allowed, if any, for completion of the entire work as stated therein, and agrees to furnish all labor, materials and services and perform all work necessary to complete any additional work specified for the consideration stated therein. Submission of sums which have no basis in fact or which Contractor knows are false are at the sole risk of Contractor and may be a violation of the False Claims Act set forth under Government Code section 12650 et seq.

This change order is subject to approval by the governing board of this District and must be signed by the District. Until such time as this change order is approved by the District's governing board and executed by a duly authorized District representative, this change order is not effective and not binding.

It is expressly understood that the compensation and time, if any, granted herein represent a full accord and satisfaction for any and all time and cost impacts of the items herein, and Contractor waives any and all further compensation or time extension based on the items herein. The value of the extra work or changes expressly includes any and all of the Contractor's costs and expenses, and its subcontractors, both direct and indirect, resulting from

4. The following claims are disputed (hereinafter, the "Disputed Claims") and are specifically excluded from the operation of this Agreement and Release:

Claim No.	Description of Claim	Amount of Claim	Date Claim Submitted
		$_____	_____
		$_____	_____
		$_____	_____
		$_____	_____
		$_____	_____
		$_____	_____

[If further space is requi$ f2&8m(ui$)123.7 (im)]TJ0 Tc aC BT /P <<6 ( )]TJ 10.Ehc

9. All rights of District shall survive completion of the Work or termination of Contract, and execution of this Release.

* * * CAUTION: THIS IS A RELEASE - READ BEFORE EXECUTING * * *

SACRAMENTO CITY UNIFIED SCHOOL DISTRICT

Signature: _____

Print Name: _____

Title: _____

CONTRACTOR: _____

Signature: _____

Print Name: _____

Title: _____

END OF DOCUMENT

DOCUMENT 00 65 36

GUARANTEE FORM
(Print on Contractor/Subcontractor Letterhead)

[Contractor's Name] hereby unconditionally guarantees that the Work performed at Joseph Bonnheim ES Telecenter Upgrades 0183-464 has been done in accordance with the requirements of the Contract therefore and further guarantees the Work of the contract to be and remain free of defects in workmanship and materials for a period of two (2) years from and after the recordation of the Notice of Completion of the Project and completion of all Contract obligations by the Contractor, including formal acceptance of the entire Project by the District, unless a longer guarantee period is called for by the Contract Documents, in which case the terms of the

DOCUMENT 00 72 13

TABLE OF CONTENTS

			Page
1.	CONTRACT TERMS AND DEFINITIONS		.1
	1.1	Definitions	1
	1.2	Laws Concerning the Contract	..6
	1.3	No Oral Agreements	7
	1.4	No Assignment	7
	1.5	Notice and Service Thereof	.7
	1.6	No Waiver	7
	1.7	Substitutions for Specified Items	8
	1.8	Materials and Work	.9
2.	[RESERVED]		.. 11
3.	LOW VOLTAGE CONSULTANT		11
4.	CONSTRUCTION MANAGER		12
5.	INSPECTOR, INSPECTIONS, AND TESTS		12
	5.1	Project Inspector	12
	5.2	Tests and Inspections	13
	5.3	Costs for After Hours an...	...2Oi0.6.(.)0.6.(.)0.5 (.)0.5Oference ( )T26 0.0040Tc 0.0..2

SACRAMENTO CITY USD GENERAL
Joseph Bonnheim ES Telecenter
Upgrades

11.10 Notification 34

11.11 Hazardous Materials 35

11.12 No Signs 35

12. TRENCHES..... 35

12.1 Trenches Greater Than Five Feet 35

12.2 Excavation Safety 35

12.3 No Tort Liability of District 35

12.4 No Excavation without Permits 35

12.5 Discovery of Hazardous Waste and/or Unusual Conditions 35

13. INSURANCE AND BONDS 36

13.1 36 0 Haz 1 13.36 T w . . . . .0 . . . 3 . 2 - . . . . . T . d . [..(....4....5.. C ....

20.1 Completion 67

20.2 Close-Out/Certification Procedures 67

20.3 Final Inspection ....

25.5 Claim Resolution pursuant to Public Contract Code section 9204 80

25.6 Subcontractor Pass-Through Claims 82

25.7 Government Code Claim Act Claim 82

25.8 Claim Resolution pursuant to Public Contract Code section 20104 et seq 83

25.9 Claim Procedure 84

. . 0.0993 0 0 1 72 688.73 cm /Im2 Do Q q 1 0 0 1 72 688.73 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 686.736 Tm 0 0 Td [(25.9 Claim Procedure)] TJ ET q 1 0 0 1 72 686.736 cm /Im3 Do Q q 1 0 0 1 72 686.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 684.736 Tm 0 0 Td [(25.10 Civil Actions)] TJ ET q 1 0 0 1 72 684.736 cm /Im4 Do Q q 1 0 0 1 72 684.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 682.736 Tm 0 0 Td [(25.11 Arbitration)] TJ ET q 1 0 0 1 72 682.736 cm /Im5 Do Q q 1 0 0 1 72 682.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 680.736 Tm 0 0 Td [(25.12 Mediation)] TJ ET q 1 0 0 1 72 680.736 cm /Im6 Do Q q 1 0 0 1 72 680.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 678.736 Tm 0 0 Td [(25.13 Jurisdiction)] TJ ET q 1 0 0 1 72 678.736 cm /Im7 Do Q q 1 0 0 1 72 678.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 676.736 Tm 0 0 Td [(25.14 Interest)] TJ ET q 1 0 0 1 72 676.736 cm /Im8 Do Q q 1 0 0 1 72 676.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 674.736 Tm 0 0 Td [(25.15 Attorneys Fees)] TJ ET q 1 0 0 1 72 674.736 cm /Im9 Do Q q 1 0 0 1 72 674.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 672.736 Tm 0 0 Td [(25.16 Waiver)] TJ ET q 1 0 0 1 72 672.736 cm /Im10 Do Q q 1 0 0 1 72 672.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 670.736 Tm 0 0 Td [(25.17 Rights and Remedies)] TJ ET q 1 0 0 1 72 670.736 cm /Im11 Do Q q 1 0 0 1 72 670.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 668.736 Tm 0 0 Td [(25.18 Survival)] TJ ET q 1 0 0 1 72 668.736 cm /Im12 Do Q q 1 0 0 1 72 668.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 666.736 Tm 0 0 Td [(25.19 Severability)] TJ ET q 1 0 0 1 72 666.736 cm /Im13 Do Q q 1 0 0 1 72 666.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 664.736 Tm 0 0 Td [(25.20 Limitation of Actions)] TJ ET q 1 0 0 1 72 664.736 cm /Im14 Do Q q 1 0 0 1 72 664.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 662.736 Tm 0 0 Td [(25.21 Construction)] TJ ET q 1 0 0 1 72 662.736 cm /Im15 Do Q q 1 0 0 1 72 662.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 660.736 Tm 0 0 Td [(25.22 Counterparts)] TJ ET q 1 0 0 1 72 660.736 cm /Im16 Do Q q 1 0 0 1 72 660.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 658.736 Tm 0 0 Td [(25.23 Entire Agreement)] TJ ET q 1 0 0 1 72 658.736 cm /Im17 Do Q q 1 0 0 1 72 658.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 656.736 Tm 0 0 Td [(25.24 Amendments)] TJ ET q 1 0 0 1 72 656.736 cm /Im18 Do Q q 1 0 0 1 72 656.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 654.736 Tm 0 0 Td [(25.25 Governing Law)] TJ ET q 1 0 0 1 72 654.736 cm /Im19 Do Q q 1 0 0 1 72 654.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 652.736 Tm 0 0 Td [(25.26 Assignment)] TJ ET q 1 0 0 1 72 652.736 cm /Im20 Do Q q 1 0 0 1 72 652.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 650.736 Tm 0 0 Td [(25.27 Successors)] TJ ET q 1 0 0 1 72 650.736 cm /Im21 Do Q q 1 0 0 1 72 650.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 648.736 Tm 0 0 Td [(25.28 Third Party Beneficiaries)] TJ ET q 1 0 0 1 72 648.736 cm /Im22 Do Q q 1 0 0 1 72 648.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 646.736 Tm 0 0 Td [(25.29 Duty to Cooperate)] TJ ET q 1 0 0 1 72 646.736 cm /Im23 Do Q q 1 0 0 1 72 646.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 644.736 Tm 0 0 Td [(25.30 Duty to Warn)] TJ ET q 1 0 0 1 72 644.736 cm /Im24 Do Q q 1 0 0 1 72 644.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 642.736 Tm 0 0 Td [(25.31 Duty to Keep Informed)] TJ ET q 1 0 0 1 72 642.736 cm /Im25 Do Q q 1 0 0 1 72 642.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 640.736 Tm 0 0 Td [(25.32 Duty to Provide Access)] TJ ET q 1 0 0 1 72 640.736 cm /Im26 Do Q q 1 0 0 1 72 640.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 638.736 Tm 0 0 Td [(25.33 Duty to Maintain Records)] TJ ET q 1 0 0 1 72 638.736 cm /Im27 Do Q q 1 0 0 1 72 638.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 636.736 Tm 0 0 Td [(25.34 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 636.736 cm /Im28 Do Q q 1 0 0 1 72 636.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 634.736 Tm 0 0 Td [(25.35 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 634.736 cm /Im29 Do Q q 1 0 0 1 72 634.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 632.736 Tm 0 0 Td [(25.36 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 632.736 cm /Im30 Do Q q 1 0 0 1 72 632.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 630.736 Tm 0 0 Td [(25.37 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 630.736 cm /Im31 Do Q q 1 0 0 1 72 630.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 628.736 Tm 0 0 Td [(25.38 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 628.736 cm /Im32 Do Q q 1 0 0 1 72 628.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 626.736 Tm 0 0 Td [(25.39 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 626.736 cm /Im33 Do Q q 1 0 0 1 72 626.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 624.736 Tm 0 0 Td [(25.40 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 624.736 cm /Im34 Do Q q 1 0 0 1 72 624.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 622.736 Tm 0 0 Td [(25.41 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 622.736 cm /Im35 Do Q q 1 0 0 1 72 622.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 620.736 Tm 0 0 Td [(25.42 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 620.736 cm /Im36 Do Q q 1 0 0 1 72 620.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 618.736 Tm 0 0 Td [(25.43 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 618.736 cm /Im37 Do Q q 1 0 0 1 72 618.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 616.736 Tm 0 0 Td [(25.44 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 616.736 cm /Im38 Do Q q 1 0 0 1 72 616.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 614.736 Tm 0 0 Td [(25.45 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 614.736 cm /Im39 Do Q q 1 0 0 1 72 614.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 612.736 Tm 0 0 Td [(25.46 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 612.736 cm /Im40 Do Q q 1 0 0 1 72 612.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 610.736 Tm 0 0 Td [(25.47 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 610.736 cm /Im41 Do Q q 1 0 0 1 72 610.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 608.736 Tm 0 0 Td [(25.48 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 608.736 cm /Im42 Do Q q 1 0 0 1 72 608.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 606.736 Tm 0 0 Td [(25.49 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 606.736 cm /Im43 Do Q q 1 0 0 1 72 606.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 604.736 Tm 0 0 Td [(25.50 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 604.736 cm /Im44 Do Q q 1 0 0 1 72 604.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 602.736 Tm 0 0 Td [(25.51 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 602.736 cm /Im45 Do Q q 1 0 0 1 72 602.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 600.736 Tm 0 0 Td [(25.52 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 600.736 cm /Im46 Do Q q 1 0 0 1 72 600.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 598.736 Tm 0 0 Td [(25.53 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 598.736 cm /Im47 Do Q q 1 0 0 1 72 598.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 596.736 Tm 0 0 Td [(25.54 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 596.736 cm /Im48 Do Q q 1 0 0 1 72 596.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 594.736 Tm 0 0 Td [(25.55 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 594.736 cm /Im49 Do Q q 1 0 0 1 72 594.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 592.736 Tm 0 0 Td [(25.56 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 592.736 cm /Im50 Do Q q 1 0 0 1 72 592.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 590.736 Tm 0 0 Td [(25.57 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 590.736 cm /Im51 Do Q q 1 0 0 1 72 590.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 588.736 Tm 0 0 Td [(25.58 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 588.736 cm /Im52 Do Q q 1 0 0 1 72 588.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 586.736 Tm 0 0 Td [(25.59 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 586.736 cm /Im53 Do Q q 1 0 0 1 72 586.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 584.736 Tm 0 0 Td [(25.60 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 584.736 cm /Im54 Do Q q 1 0 0 1 72 584.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 582.736 Tm 0 0 Td [(25.61 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 582.736 cm /Im55 Do Q q 1 0 0 1 72 582.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 580.736 Tm 0 0 Td [(25.62 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 580.736 cm /Im56 Do Q q 1 0 0 1 72 580.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 578.736 Tm 0 0 Td [(25.63 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 578.736 cm /Im57 Do Q q 1 0 0 1 72 578.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 576.736 Tm 0 0 Td [(25.64 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 576.736 cm /Im58 Do Q q 1 0 0 1 72 576.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 574.736 Tm 0 0 Td [(25.65 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 574.736 cm /Im59 Do Q q 1 0 0 1 72 574.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 572.736 Tm 0 0 Td [(25.66 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 572.736 cm /Im60 Do Q q 1 0 0 1 72 572.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 570.736 Tm 0 0 Td [(25.67 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 570.736 cm /Im61 Do Q q 1 0 0 1 72 570.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 568.736 Tm 0 0 Td [(25.68 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 568.736 cm /Im62 Do Q q 1 0 0 1 72 568.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 566.736 Tm 0 0 Td [(25.69 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 566.736 cm /Im63 Do Q q 1 0 0 1 72 566.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 564.736 Tm 0 0 Td [(25.70 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 564.736 cm /Im64 Do Q q 1 0 0 1 72 564.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 562.736 Tm 0 0 Td [(25.71 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 562.736 cm /Im65 Do Q q 1 0 0 1 72 562.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 560.736 Tm 0 0 Td [(25.72 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 560.736 cm /Im66 Do Q q 1 0 0 1 72 560.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 558.736 Tm 0 0 Td [(25.73 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 558.736 cm /Im67 Do Q q 1 0 0 1 72 558.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 556.736 Tm 0 0 Td [(25.74 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 556.736 cm /Im68 Do Q q 1 0 0 1 72 556.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 554.736 Tm 0 0 Td [(25.75 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 554.736 cm /Im69 Do Q q 1 0 0 1 72 554.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 552.736 Tm 0 0 Td [(25.76 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 552.736 cm /Im70 Do Q q 1 0 0 1 72 552.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 550.736 Tm 0 0 Td [(25.77 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 550.736 cm /Im71 Do Q q 1 0 0 1 72 550.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 548.736 Tm 0 0 Td [(25.78 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 548.736 cm /Im72 Do Q q 1 0 0 1 72 548.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 546.736 Tm 0 0 Td [(25.79 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 546.736 cm /Im73 Do Q q 1 0 0 1 72 546.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 544.736 Tm 0 0 Td [(25.80 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 544.736 cm /Im74 Do Q q 1 0 0 1 72 544.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 542.736 Tm 0 0 Td [(25.81 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 542.736 cm /Im75 Do Q q 1 0 0 1 72 542.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 540.736 Tm 0 0 Td [(25.82 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 540.736 cm /Im76 Do Q q 1 0 0 1 72 540.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 538.736 Tm 0 0 Td [(25.83 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 538.736 cm /Im77 Do Q q 1 0 0 1 72 538.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 536.736 Tm 0 0 Td [(25.84 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 536.736 cm /Im78 Do Q q 1 0 0 1 72 536.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 534.736 Tm 0 0 Td [(25.85 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 534.736 cm /Im79 Do Q q 1 0 0 1 72 534.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 532.736 Tm 0 0 Td [(25.86 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 532.736 cm /Im80 Do Q q 1 0 0 1 72 532.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 530.736 Tm 0 0 Td [(25.87 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 530.736 cm /Im81 Do Q q 1 0 0 1 72 530.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 528.736 Tm 0 0 Td [(25.88 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 528.736 cm /Im82 Do Q q 1 0 0 1 72 528.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 526.736 Tm 0 0 Td [(25.89 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 526.736 cm /Im83 Do Q q 1 0 0 1 72 526.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 524.736 Tm 0 0 Td [(25.90 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 524.736 cm /Im84 Do Q q 1 0 0 1 72 524.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 522.736 Tm 0 0 Td [(25.91 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 522.736 cm /Im85 Do Q q 1 0 0 1 72 522.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 520.736 Tm 0 0 Td [(25.92 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 520.736 cm /Im86 Do Q q 1 0 0 1 72 520.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 518.736 Tm 0 0 Td [(25.93 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 518.736 cm /Im87 Do Q q 1 0 0 1 72 518.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 516.736 Tm 0 0 Td [(25.94 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 516.736 cm /Im88 Do Q q 1 0 0 1 72 516.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 514.736 Tm 0 0 Td [(25.95 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 514.736 cm /Im89 Do Q q 1 0 0 1 72 514.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 512.736 Tm 0 0 Td [(25.96 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 512.736 cm /Im90 Do Q q 1 0 0 1 72 512.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 510.736 Tm 0 0 Td [(25.97 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 510.736 cm /Im91 Do Q q 1 0 0 1 72 510.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 508.736 Tm 0 0 Td [(25.98 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 508.736 cm /Im92 Do Q q 1 0 0 1 72 508.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 506.736 Tm 0 0 Td [(25.99 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 506.736 cm /Im93 Do Q q 1 0 0 1 72 506.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 504.736 Tm 0 0 Td [(25.100 Duty to Provide Notice)] TJ ET q 1 0 0 1 72 504.736 cm /Im94 Do Q q 1 0 0 1 72 504.736 cm /Compl-0.0 gs 0.8062 0.8062 0.8062 rg /GS3 gs 0 0 m 468 0 l 468 1.5 l 0 1.5 l f Q BT /F29 1 Tf 0 0 0 1 72 502.736 Tm 0 0 Td [(25.101 Duty to Provide Notice)] TJ

DOCUMENT 00 72 13

GENERAL CONDITIONS

1. CONTRACT TERMS AND DEFINITIONS

1.1 Definitions

Wherever used in the Contract Documents, the following terms shall have the meanings indicated, which shall be applicable to both the singular and plural thereof:

1.1.1 Adverse Weather : Shall be only weather that satisfies all of the following conditions: (1) unusually severe precipitation, sleet, snow, hail, or extreme temperature b0.458 04Td ( )Tj 4.002 Tc250.003 Twth168 ( )e1.5 (r)-2.8 (e)1.627 Tc 0 Tw 6.2

fontrooTh (i -18 2 (st]TJ 15 Tc206 T 4.08 2 (0 Td (2 0 Td [(T3.00 Td [(p)-20.6l)-9J 0 Tc 0 Tw 1.12 049)-9.4 (ca-0.0

1.1.31 Project: The planned undertaking as provided for in the Contract Documents. Th (o)8.6c 0.481 34.92 re W n]TJ -0.0e8176 130.44131.44131.442 (j)r1r 0.554 0 Td Tw 60 69.84 Tm

1.1.41 Samples : Physical examples that illustrate materials, products, equipment, finishes, colors, or workmanship and that, when approved in accordance with the Contract Documents, establish standards by which portions of the Work will be judged.

1.1.42 Shop Drawings : All drawings, prints, diagrams, illustrations, brochures, schedules, and other data that are prepared by the Contractor, a subcontractor, manufacturer, supplier, or distributor, that illustrate how specific portions of the Work shall be fabricated or installed.

1.1.43 Site : The Project site as shown on the Drawings.

1.1.44 Specifications : That portion of the Contract Documents, Division 1 through Division 49, and all technical sections, and addenda to all of these, if any, consisting of written descriptions and requirements of a technical nature of materials, equipment, construction methods and systems, standards, and workmanship.

1.1.45 State : The State of California.

1.1.46 Storm Water Pad <</MCI (s)716.6 (t6)92.5 (nA (caTT1 1 8.6 (si)-18.2 (s 0.952 0 Td ( )Tj (or)3 (m0

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

an approval of or acquiescence in any breach thereunder, except as may be specifically agreed in writing.

1.7 Substitutions for Specified Items

1.7.1 Whenever in the Specifications any materials, process, or article is indicated or specified by grade, patent, or proprietary name, or by name of manufacturer, that Specification shall be deemed to be followed by the words “or equal.” Contractor may, unless otherwise stipulated, offer for approval any material, process, or article that shall be equal in all respects to that specified.

1.7.4.1 The proposed substitute is equal or superior in all respects to that specified, and that such proposed substitute is suitable and fit for the intended purpose and will perform

4. CONSTRUCTION MANAGER

4.1 If a Construction Manager is used on this Project ("Construction Manager" or "CM"), the Construction Manager will provide administration of the Contract on the District's behalf. After execution of the Contract and Notice to Proceed, all correspondence and/or instructions from Contractor and/or District shall be forwarded through the Construction Manager. The Construction Manager will not be responsible for and will not have control or charge of construction means, methods, techniques, sequences, or procedures or for safety precautions in connection with the Work, which shall all remain the Contractor's responsibility.

4.2 The Construction Manager, however, will have authority to reject materials and/or workmanship not conforming to the Contract Documents, as determined by the District, the Low Voltage Consultant, and/or the Project Inspector. The Construction Manager shall also have the authority to require special inspection or testing of any portion of the Work, whether it has been fabricated, installed, or fully completed. Any decision made by the Construction Manager, in good faith, shall not give rise to any duty or responsibility of the Construction Manager to: the Contractor; any Subcontractor; the Contractor or Subcontractor's respective agents, employees; or other persons performing any of the Work. The Construction Manager shall have free access to any or all parts of Work at any time.

4.3

stoppage by the Project Inspector(s) and/or DSA shall be without liability to the District.

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

6.3 Contractor's Supervision

6.3.1 During progress of the Work, Contractor shall keep on the Premises, and at all other locations where any Work related to the Contract is being performed, an experienced and competent project manager and construction superintendent who are employees of the Contractor, to whom the District does not object and at least one of whom shall be fluent in English, written and verbal.

6.3.2 The project manager and construction superintendent shall both speak fluently the predominant language of the Contractor's employees.

6.3.3 Before commencing the Work herein, Contractor shall give written notice to District of the name of its project manager and construction superintendent. Neither the Contractor's project manager nor construction superintendent shall be changed except with prior written notice to District. If the Contractor's project manager and/or construction superintendent proves to be unsatisfactory to Contractor, or to District, any of the District's employees, agents, the Construction Manager, or the Low Voltage Consultant, the unsatisfactory project manager and/or construction superintendent shall be replaced. However, Contractor shall notify District in writing before any change occurs, but no less than two (2) business days prior. Any replacement of the project manager and/or construction superintendent shall be made promptly and must be satisfactory to the District. The Contractor's project manager and construction superintendent shall each represent Contractor, and all directions given to Contractor's project manager and/or construction superintendent shall be as binding as if given to Contractor.

6.3.4 Contractor shall give efficient supervision to Work, using its best skill and attention. Contractor shall carefully study and compare all Contract Documents, Drawings, Specifications, and other instructions and shall at once report to District, Construction Manager, and Low Voltage Consultant any error, inconsistency, or omission that Contractor or its employees and Subcontractors may discover, in writing, with a copy to District's Project Inspector(s). The Contractor shall have responsibility for discovery of errors, inconsistencies, or omissions.

6.4 Duty to Provide Fit Workers

6.4.1 Contractor and Subcontractor(s) shall at all times enforce strict discipline and good order among their employees and shall not employ or work any unfit person or anyone not skilled in work assigned to that person. It shall be the responsibility of Contractor to ensure compliance with this requirement. District may require Contractor to permanently remove unfit persons from Project Site.

6.4.2 Any person in the employ of Contractor or Subcontractor(s) whom District may deem incompetent or unfit shall be excluded from working on the Project and shall not again be employed on the Project except with the prior written consent of District.

6.4.3 The Contractor shall furnish labor that can work in harmony with all other elements of labor employed or to be employed in the Work.

6.4.4 Fingerprinting

in performance of the Work, and shall verify all dimensions and conditions on the Site. All dimensions affecting proper fabrication and installation of all Work must be verified pri or to fabrication by taking field measurements of the true conditions. If there are any discrepancies between dimensions in drawings and existing conditions which will affect the Work, Contractor shall bring such discrepancies to the attention of the District and Low Voltage Consultant for adjustment before pro56.9 ( )(g)]TJ 0 Tc 0 Tw 4.386 (o56.9 ( )

6.13.2 Contractor shall comply with all applic6 (p)11.rg3 -0 0 9.96 143.04 709.92 Tm ( )Tj /TT1 1 Tf 0.0.6 (a)

lights, and watchmen for protection of workers and the public and shall post danger signs warning against hazards created by such features in the course of construction.

6.14.8 Hazards Control – Contractor shall store volatile wastes in covered metal containers and remove them from the Site daily. Contractor shall prevent accumulation of wastes that create hazardous conditions. Contractor shall provide adequate ventilation during use of volatile or noxious substances.

6.14.9 Contractor shall designate a responsible member of its organization on the Project, whose duty shall be to post information regarding protection and obligations of workers and other notices required under occupational safety and health laws, to comply with reporting and other occupational safety requirements, and to protect the life, safety, and health of workers. Name and position of person so designated shall be reported to District by Contractor.

6.14.10 Contractor shall correct any violations of safety laws, rules, orders, standards, or regulations. Upon the issuance of a citation or notice of violation by the Di (p)-7.5 (a)-5.5 (t)-7Tw 3.036l(t)-8.6cCri.6cCrequq .6 (n(.6 (nue)0.6 (p)Tj 0.0 Tw 3.735 0 Td ( )Tj -0.0-10 Tc (

Work or item damaged. This shall include any adjoining property of the District and others.

6.14.17 Contractor shall take adequate precautions to protect existing roads, sidewalks, curbs, pavements, utilities, adjoining property, and structures (including, without limitation, protection from settlement or loss of lateral support), and to avoid damage thereto, and repair any damage thereto caused by construction operations.

6.14.18 Contractor shall confine apparatus, the storage of materials, and the operations of workers to limits indicated by law, ordinances, permits, or directions of

low Voltage Conw6 (t (t)-7.5 (a)-564 (t)-7.6 (s)]TJ 0t.004 Tc 0.005 Tw 0.336 0 11.16(o)0.6 (,)0.6 (th)-1.5(c)-2 (t (t)-8

necessary for protecting and securing the Work, all school occupants, furnishings, equipment, and building structure from damage until its completion and final acceptance by District. Dust barriers shall be provided to isolate dust and dirt from construction operations. At completion of the Work and portions thereof, Contractor shall clean to the original state any areas beyond the Work area that become dust laden as a result of the Work. The Contractora(u)-10.6 (lsu)-10.6 9 4.6 (e)-11.4 (80 Tw 1 -0.005 Tc 9(te.1 (6 (

a (t)-8.5 gra(u)-10.6be86.4 reg (t)-8.5 grae (rk)-4.8 (e)0.7 ((u)-10.6w -2.1 (e)0.

Contractor and its Subcontractor(s) or between Subcontractors.

7.9 Contractor must include in all of its subcontracts the assignment provisions as indicated in the Termination section of these General Conditions.

8. OTHER CONTRACTS/CONTRACTORS

8.1 District reserves the right to let other contracts, and/or to perform work with

9.

detail to serve as the basis for progress payments during construction. Unless the Special Conditions contain different limits, this preliminary schedule of values shall include, at a minimum, the followin r fnirb.68(o)10.6 (l)-9.2 (l)-9.2 (o)10.6 (w)16.8 (i)-9.2 ID 11 >>BD7C. (

10.1.1.2.6 The preliminary schedule of values shall be subject to the District's review and approval of the form and content thereof. In the event that the District objects to any portion of the preliminary schedule of values, the District shall notify the Contractor, in writing, of the District's objection(s) to the preliminary schedule of values. Within five (5) calendar days of the date of the District's written objection(s), Contractor shall submit a revised preliminary schedule of values to the District for review and approval. The foregoing procedure for the preparation, review and approval of the preliminary schedule of values sha ll continue until the District has approved the entirety of the preliminary schedule of values.

10.1.1.2.7 Once the preliminary schedule of values is approved by the District, this shalsttric ryd n tithe

10.1.3

10.4 Submittals

10.4.1 Low Voltage Consultant 's favorable review shall neither be construed as a complete check nor relieve the Contractor, Subcontractor, manufacturer, fabricator, or supplier from responsibility for any deficiency that may exist or from any departures or deqj ET Q q0.6 (23Ia0 Tw 1.639 0 Td ( )Tj -0.005 Tc 0.005 Tw 0.325 0 Td [(C)-17.8 (on)-10.5 (t)-8.6 (

d23Ia6..1 (yh)(6 (ru11or)0.6 (a)-6.420 Tw 1.025 (c.6 15(a)-6.4 (.10 (a)-50 Td (w.1 (i)-20.325 (c)6.9 (o)8.6[(C)-12 (a

unknown conditions of an unusual nature that differ materially from those ordina rily encountered in the work of the character provided for in Plans and Specifications, except as indicated in the provisions of these General Conditions regarding trenches, trenching, and/or existing utility lines.

11.3 Access to Work

District and its repres entatives shall at all times have access to Work wherever it is in preparation or progress, including storage and fabrication. Contractor shall provide safe and proper facilities for such access so that District's representatives may perform their functions.

11.4 Layout and Field Engineering

11.4.1 All field engineering required for layout of this Work and establishing grades for earthwork operations shall be furnished by Contractor at its expense. This Work shall be done by a qualified, California - registered civil engineer approved in writing by District and Low Voltage Consultant . Any required Record and/or As-Built Drawings of Site development shall be prepared by the approved civil engineer.

11.4.2 The Contractor shall be responsible for having ascertained pertinent local conditions such as location, accessibility, and general character of the Site and for having satisfied itself as to the conditions under which the Work is to be performed. Contractor shall follow best practices, including but not limited to potholing to avoid utilities. District shall not be liable for any claim for allowances because of Contractor's error, failure to follow best practices, or

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

the condition(s).

11.11 Hazardous Materials

Contractor shall

Site of the Project, is not protected under the Workers' Compensation Insurance,

Contractor shall provide, or shall cause a Subcontractor to provide, adequate insurance coverage for the protection of any employee(s) not otherwise protected before any of those employee(s) commence work.

13.1.5 Builder's Risk Iran

Contractor hereby acknowledges and agrees that all insurance carried by it shall be deemed liability coverage for all actions it performs in connection with the Contract.

13.2 Contract Security - Bonds

13.2.1 Contractor shall furnish two surety bonds issued by a California admitted surety insurer as follows:

13.2.1.1 Performance Bond: A bond in an amount at least equal to one hundred percent (100%) of Contract Price as security for faithful performance of this Contract.

13.2.1.2 Payment Bond: A bond in an amount at least equal to one hundred

14.1.3 If, in the opinion of District, defective work creates a dangerous condition or requires immediate correction or attention to prevent further loss to District or to preve nt interruption of District operations, District will attempt to give the notice required above. If Contractor or Surety cannot be contacted or [illegible] 9-10.c 8c 8-99.6 4-10.nu (g)0.f

of the Indemnitees' and/or Low Voltage Consultant 's liability to the extent caused by the sole negligence, active negligence, or willful misconduct of the Indemnitees, and/or defects in design furnished by the Low Voltage Consultant, as found by a court or arbitrator of competent jurisdiction. The District shall have the right to accept or reject any legal representation that Contractor proposes to defend the Indemnitees. If any Indemnitee provides its own defense due to failure to timely respond to tender of defense,

survive the completion of Work, the warranty/guarantee period, and the termination of the Contract.

15. TIME

15.1 Notice to Proceed

15.1.1 District may issue a Notice to Proceed within ninety (90) days from the date of the Notice of Award. Once Contractor has received the Notice to Proceed, Contractor shall complete the Work within the period of time indicated in the Contract Documents.

15.1.2 In the event that the District desires to postpone issuing the Notice to Proceed beyond ninety (90) days from the date of the Notice of Award, it is expressly understood that with reasonable notice to the Contractor, the District may postpone issuing the Notice to Proceed. It is further expressly understood by Contractor that Contractor shall not be entitled to any claim of additional compensation as a result of the postponement of the issuance of the Notice to Proceed.

15.1.3 If the Contractor believes that a postponement of issuance of the Notice to Proceed will cause a hardship to Contractor, Contractor may terminate the Contract. Contractor's termination due to a postponement shall be by written notice to District

these General Conditions of any anticipated delay and its cause. Following submission of a claim, the District may determine whether the delay is to be considered avoidable or unavoidable, how long it continues, and to what extent the prosecution and completion of the Work might be delayed thereby.

16.2.3 In the event the Contractor requests an extension of Contract Time for unavoidable delay, such request shall be submitted in accordance with the provisions in the Contract Documents governing changes in Work. When requesting time, requests must be submitted with full justification and documentation. If the Contractor fails to submit justification, it waives its right to a time extension at a later date. Such justification must be based on the official Construction Schedule as updated at the time of occurrence of the delay or execution of Work related to any changes to the Scope of Work. Any claim for delay must include the following information as support, without limitation:

16.2.3.1 The duration of the activity relating to the changes in the Work and the resources (manpower, equipment, material, etc.) required to perform the activities within the stated duration.

16.2.3.2 Specific logical ties to the Contract Schedule for the proposed changes and/or delay showing the activity/activities in the Construction Schedule that are affected by the change and/or delay. In particular, Contractor must show an actual impact to the schedule, after making a good faith effort to mitigate the delay by rescheduling the work, by providing an analysis of the schedule ("Time Impact Analysis"). Such Time Impact Analysis shall describe in detail the cause and effect of the delay and the impact on the critical dates in the Project

22a t orca2-1,6-2n4an. doc

16.3.2.4 The delay could not have been avoided or mitigated by Contractor's reasonable diligence; and

16.3.2.5 Contractor timely complies with the claims procedure of the Contract

fully responsible for any and all delays and/or expenses caused by Contractor's failure to expeditiously perform this Work.

17.1.3 Should any Change Order result in an increase in the Contract Price or extend the Contract Time, the cost of or length of extension in that Change Order shall be agreed to, in writing, by the District in advance of the Work by Contractor, and shall be subject to the monetary limitations set f orth in Public Contract Code section 20118.4. In the event that Contractor proceeds with any change in Work without a Change Order executed by the District or Construction Change Directive, Contractor waives any claim of additional compensation or time for that additional work. Under no circumstances shall Contractor be entitled to any claim of additional compensation or time not expressly requested by Contractor in a Proposed Change Order or approved by District in an executed Change Order.

17.1.4 A Change Order or Construction Change Directive will become effective when approved by the Board, notwithstanding that Contractor has not signed it. A Change Order or Construction Change Directive will become effective without Contractor's signature provided District in dicates it as a "Unilateral Change Order". Any dispute as to the adjustment in the Contract Price or Contract Time, if any, of the Unilateral Change Order shall be resolved pursuant to the Payment and Claims and Disputes provisions herein.

17.1.5 Contractor understands, acknowledges, and agrees that the reason for District authorization is so that District may have an opportunity to analyze the Work and decide whether the District shall proceed with the Change Order or alter the Project so that a change in Wo rk becomes unnecessary.

17.2 Low Voltage Consultant Authority

.0897 (7) 3089 6 15 Thomas 9325 0897 (rac per 67 [illegible] 8438 es 9 716 [illegible] 0 7 [illegible] 1 [illegible] 4 [illegible] 9 [illegible] 1 [illegible] 5 [illegible] 6 [illegible] 4 [illegible] 0 [illegible] 7 [illegible] 2 [illegible] 8 [illegible] 2 [illegible] 7 [illegible] 6

The Low Voltage Consultant

17.4 Construction Change Directives

17.4.1 A Construction Change Directive is a written order prepared and issued by the District, the Construction Manager, and/or the Low Voltage Consultant and signed by the District and the Low Voltage Consultant, directing a change in the Work. The District may, as provided by law, by Construction Change Directive and without invalidating the Contract, order changes in the Work consisting of additions, deletions, or other revisions. The adjustment to the Contract Price or Time, if any, is subject to the provisions of this section regarding Changes in the Work. If all or a portion of the Project is being funded by funds requiring approval by the State Allocation Board ("SAB"), these revisions may be subject to compensation once approval of same is received and funded by the SAB, and funds are released by the Office of Public School Construction ("OPSC"). Any dispute as to the adjustment in the Contract Price, if any, of the Construction Change Directive or timing of payment shall be resolved pursuant to the Payment and Claims and Disputes provisions herein.

17.4.2 The District may issue a Construction Change Directive in the absence of agreement on the terms of a Change Order.

17.5 Force Account Directives

17.5.1 When work, for which a definite price has not been agreed upon in advance, is to be paid fo

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

in accordance with the provisions of the Contract Documents, and the Contractor submits the cost and/or request for extension of time recognizing the significant civil penalties and treble damages which follow from making a false claim or presenting a false claim under Government Code section 12650 et seq .

It is expressly understood that the value of the extra Work or changes expressly includes any and all of the Contractor's costs and expenses, direct and indirect, resulting from additional time required on the Project or ndirect,

17.8 Format for Proposed Change Order

17.8.1 The following format shall be used as applicable by the District and the Contractor (e.g. Change Orders, PCO's) to communicate proposed additions and deductions to the Contract, supported by attached documentation. Any spaces left blank will be deemed no change to cost or time.

	WORK PERFORMED OTHER THAN BY CONTRACTOR	ADD	DEDUCT
(a)	Material (attach suppliers' invoice or itemized quantity and unit cost plus sales tax)		
(b)	Add Labor (attach itemized hours and rates, fully Burdened, and specify the hourly rate for each additional labor burden, for example, payroll taxes, fringe benefits, etc.)		
(c)	Add Equipment (attach suppliers' invoice)		
(d)	Subtotal		
(e)	Add Overhead and Profit for any and all tiers of Subcontractor, the total not to exceed ten percent (10%) of Item (d)		
(f)	Subtotal		
(g)	Add General Conditions Cost (if Time is Compensable) (attach supporting documentation)		
(h)	Subtotal		
(i)	Add Overhead and Profit for Contractor, not to exceed five percent (5%) of Item (h)		
(j)	Subtotal		
(k)	Add Bond and Insurance, not to exceed two p	28 374.47W	

17.8.2 Labor .

Contractor shall be compensated for the costs of labor actually and directly utilized in the performance of the Work. Such labor costs shall be the actual cost, use of any formulas (e.g. labor factors) is not allowed, not to exceed prevailing wage rates in the locality of the Site and shall be in the labor classification(s) necessary for the performance of the Work, fully Burdened. Labor costs shall exclude costs incu rred by the Contractor in preparing estimate(s) of the costs of the change in the Work, in the maintenance of records relating to the costs of the change in the Work, coordination and assembly of materials and information relating to the change in the Work or performance thereof, or the supervision and other overhead and general conditions costs associated with the change in the Work or performance thereof,

rental time. The foregoing notwithstanding, neither moving time or loading and transportation time shall be allowed if the Equipment is used for performance of any portion of the Work other than the change in the Work. Unless prior approval in writing is obtained by the Contractor from the Low Voltage Consultant , the Project Inspector and the District, no costs or compensation shall be allowed for time while Construction Equipment is inoperative, idle or on standby, for any reason. Contractor shall not be entitled to an allowance or any other compensation for Equipment or tools used in the performance of change in the Work where such Equipment or tools have a replacement value of $500.00 or less. Equipment costs

the changes herein to the Contract shall only be effective when approved by the governing board of the District.

17.9.1.2 It is expressly understood that the value of the extra Work or changes expressly includes any and all of the Contractor's cost (r)9.3 (')89fltTd ((e)9.9.6 (s.96 -6 (c)-5.1 (o)8.6 (s (g)0.

parties agree to a different price and the Contract Time shall be adjusted by the number of days allocated in the Contract Documents. If days are not allocated in the Contract Documents, the Contract Time shall be equitably adjusted.

17.13 Discounts, Rebates, and Refunds

For purposes of determining the cos 1.6f.9 (y)5.6f.9 (y)5.6f.9 (y).004 10.004 Tw 0[(p)-8.5 (a)-m2 Tm [(F)-7.f4M>>B

execute finalized Change Orders and proceed under the provisions herein with proper notice.

17.18 Failure of Contractor to Execute Change Order

Contractor shall be in default of the Co ntract if Contractor fails to execute a Change Order when the Contractor agrees with the addition and/or deletion of the Work in that Change Order.

18. REQUEST FOR INFORMATION

18.1 Any Request for Information shall reference all applicable Contract Document(s), including Specification section(s), detail(s), page number(s), drawing number(s), and sheet number(s), etc. The Contractor shall make suggestions and interpretations of the issue raised by each Request for Information. A Request for Information cannot modi fy the Contract Price, Contract Time, or the Contract Documents. Upon request by the District, Contractor shall provide an electronic copy of the Request for Information in addition to the hard copy.

18.2 The Contractor shall be responsible for any costs incurred for professional services that District may deduct from any amounts owing to the Contractor, if a Request for Information requests an interpretation or decision of a matter where the information sought is equally available to the party making the request. District, at its sole discretion, shall deduct from and/or invoice Contractor for all the professional services arising herein.

19.2.1.1.1.14 A certification by the Contractor of the

19.3.1.1 Upon receipt of an Application for Payment, The District shall act in accordance with both of the following:

19.3.1.1.1 Each Application for Payment

said estimate shall operate to release the Contractor, or any Surety upon any bond, from damages arising from such Work, or from the District's right to enforce each and every provision of this Contract, and the District shall have the right subsequently to correct any error made in any estimate for payment.

19.3.2.2 The Contractor shall not be entitled to have any payment requests processed, or be entitled to have any payment made for Work performed, so long as any lawful or proper direction given by the District concerning the Work, or any portion thereof, remains incomplete.

19.3.2.3 If the District fails to make any progress payment within thirty (30) days after receipt of an undisputed and properly submitted Application for Payment from the Contractor, the District shall pay interest to the Contractor equivalent to the legal rate set forth in subdivision (a) of Section 685.010 of the Code of Civil Procedure.

19.3.3 No Waiver

No payment by District hereunder shall be interpreted so as to imply that District has inspected, approved, or accepted any part of the Work. Notwithstanding any payment, the District may enforce each and every provision of this Contract. The District may correct or require correction of any error subsequent to any payment.

19.4 Decisions to Withhold Payment

19.4.1 Reasons to Withhold Payment

The District may withhold payment in whole, or in part, to the extent reasonably necessary to protect the District if, in the District's opinion, the representations to the District required herein cannot be made. The District may withhold payment, in whole, or in part, to such extent as may be necessary to protect the District from loss because of, but not limited to any of the following:

19.4.1.1 Defective Work not remedied within FORTY - EIGHT (48) hours of written notice to Contractor.

19.4.1.2 Stop Payment Not.8 (o)8.6 ( )Tj /TT1 1 Tf 0.004 Tc -0.006 Tw 9.96 0 0 9.96 184.23 0 Td [(n)c -0

19.4.1.21 Failure to pay Subcontractor(s) or supplier(s) as required by law and by the Contract Documents.

19.4.1.22 Failure to pay any royalty, license or similar fees.

19.4.1.23 Contractor is otherwise in breach, default, or in substantial violation of any provision of this Contract.

19.4.1.24 Failure to perform any implementation and/or monitoring required by any SWPPP for the Project and/or the imposition of an y penalties or fines therefore whether imposed on the District or Contractor.

19.4.2 Reallocation of Withheld Amounts

19.4.2.1 District may, in its discretion, apply any withheld amount to pay outstanding claims or obligations as defined herein. In so doing, District shall make such payments on behalf of Contractor. If any payment is so made by District, then that amount shall be considered a payment made under Contract by District to Contractor and District shall not be liable to Contractor for any payment made in goo d faith. These payments may be made without prior judicial determination of claim or obligation. District will render Contractor an accounting of funds disbursed on behalf of Contractor.

19.4.2.2 If Contractor defaults or neglects to carry out the Work in accordan ce

19.5.2 No Obligation of District for Subcontractor Payment

The District shall have no obligation to pay, or to see to the payment of, money to a Subcontractor except as may otherwise be required by law.

19.5.3 Joint Checks

District shall have the right in its sole discretion, if necessary for the protection of the District, to issue joint checks made payable to the Contractor and Subcontractors and/or material or equipment suppliers.

Work is ready for final inspection an d District acceptance, Low Voltage Consultant and Project Inspector will inspect the Work and shall submit to Contractor and District a final inspection report noting the Work, if any, required in order to complete in accordance with the Contract Documents. Absent unusual circumstances, this report shall consist of the Punch List items not yet satisfactorily completed.

20.3.2 Upon Contractor's completion of all items on the Punch List and any other uncompleted portions of the Work, the Contractor shall n otify the District and Low Voltage Consultant, who shall again inspect such Work. If the Low Voltage Consultant finds the Work complete and acceptable under the Contract Documents, B.5-11.7 (a)2.6b]TJ 0.1.-Ca

20.4 Costs of Multiple Inspections

More than two (2) requests of the District to make a final inspection shall be considered an additional service of District, Low Voltage Consultant, Construction Manager, and/or Project Inspector, and all subsequent costs will be invoiced to Contractor and if funds are available, withheld from remaining pa yments.

20.5 Partial Occupancy or Use Prior to Completion

20.5.1 District's Rights to Occupancy

The District may occupy or use any completed or partially completed portion of the Work at any stage, and such occupancy shall not constitute the District's Final Acceptance of any part of the Work. Neither the District's Final Acceptance, the making of Final Payment, any provision in Contract Documents, nor the use or occupancy of the Work, in whole or in part, by District shall constitute acceptance of Work not in accordance with the Contract Documents nor relieve the Contractor or the Contractor's Performance Bond Surety from liability with respect to any warranties or responsibility for faulty or defective Work or materials, equipment and workmanship incorporated therein. In the event that the District occupies or uses any completed or partially completed portion of the Work, the Contractor shall

items have been satisfactorily completed), the District shall record a Notice of Completion with the County Recorder, and the Contractor shall, upon receipt of final payment from the District, pay the amount due Subcontractors.

21.2 Prerequisites for Final Payment

The following conditions must be fulfilled prior to Final Payment:

21.2.1 A full release of all Stop Payment Notices served in connection with the Work shall be submitted by Contractor.

21.2.2 A duly completed and executed conditional

SACRAMENTO

24.2.2.1

24.3.2.3 Terminate all existing subcontracts and purchase orders and enter into no further subcontracts and purchase orders.

24.3.3 Within 30 days of the notice, Contractor submit to the District a payment application for the actual cost for labor, materia ls, and services performed, including all Contractor's and Subcontractor(s)' mobilization and/or demobilization costs, that is unpaid. Contractor shall have no claims against the District except for the actual cost for labor, materials, and services performed that adequately documented through timesheets, invoices, receipts, or otherwise. District shall pay all undisputed invoice(s) for work performed until the notice of termination.

24.3.4 Under a termination for convenience, the District retains the right to all the options available to the District if there is a termination for cause.

24.4 Effect of Termination

24.4.1 Contractor shall, only if ordered to do so by the District, immediately remove from the Site all or any materials and personal property belonging to Contractor that have not been incorporated in the construction of the Work, or which are not in place in the Work. The D-0 0 9.96roate insTJ -0.004 Tc orr Distrin.6 (D)3.t, otr oaCdoel ning0.6 (d)]T

SACRAMENTO

25.3.1.1 A time extension, including without limitation, for relief of damages or penalties for delay assessed by the District under the Contract;

25.3.1.2 Payment by the of 5-9.49g0.0.5 (f)-2.16ns1 5-9.4-2(2)8.28()-1v1e D56810.7 (2)8.2(.1)-3.4-2(

25.4.1.3.1 The undersigned Contractor certifies under penalty of perj

statement. Amounts not paid in a timely manner as required by this section, section 25.4, shall bear interest at seven percent (7%) per annum.

25.5.1.2 Upon req 0.7 8q3.5 6 39 8gLBody <<f 4 4 2 acve9128422.6 9.96 10.337 0 Td (a)Tj 6003 Tw 0.

dispute resolution through negotiation or by issuance of an evaluation. Any mediation utilized shall conform to the timeframes in this section.

25.5.3.2 Unless otherwise agreed to by the District and Contractor in writing, the mediation conducted pursuant to this section shall excuse any further obligation under Public Contract Code section 20104.4 to mediate after litigation has been commenced.

25.5.4 STEP 4:

25.5.4.1 If mediation under this section does not resolve the parties' dispute, the District may, but does not require arbitration of disputes under private arbitration or the Public Works Contract Arbitration Program.

25.6 Subcontractor Pass - Through Claims

25.6.1 If a subcontractor or a lower tier subcontractor lacks legal standing to assert a claim against a District because privi

and confer process, including any period of time utilized by the meet and confer process.

25.8 Claim Resolution pursuant to Public Contract Code

SACRAMENTO

signed change order approved as to form by legal counsel for both District and Contractor; norm ccrm o 0.005 TiW n BT / (n)-10.6 (e)0.r521.4 S9g58 ( )c 0 Tw 85rmct

SACRAMENTO CITY USD GENERAL
Joseph Bonnheim ES Telecenter
Upgrades

26.5

26.5.7.2 Forfeit as a penalty to District the full amount as stated in Labor Code section 1777.7. Interpretation and enforcement of these provisions shall be in accordance with the rules and procedures of the California Apprenticeship Council and under the authority of the Chief of the Division of Apprenticeship Standards.

26.5.8 Contractor and all Subcontractors shall comply with Labor Code section 1777.6, which section forbids certain discriminatory practices in the employment of apprentices.

26.5.9 Contractor shall become fully acquainted with the law regarding apprentices prior to commencement of the Work. Special attention is directed to sections 1777.5, 1777.6, and 1777.7 of the Labor Code, and title 8, California Code of Regulations, section 200 et seq. Questions may be directed to the State Division of Apprenticeship Standards, 455 Golden Gate Avenue, 9th floor, San Francisco, emaBQC0.349 0(aBQC0.34)Tj (

tenders final payment to the Contractor, without further acknowledgment by the parties.

28.1.2 Section 4552 of the Government Code states:

In submitting a bid to a public purchasing body, the bidder offers and agrees that if the bid is accepted, it will assign to the purchasing body all rights, title, and interest in and to all causes of action it may have under Section 4 of the Clayton Act (15 U.S.C. Sec. 15) or under the Cartwright Act (Chapter 2 (commencing with Section 16700) of Part 2 of Division 7 of the Business and Professions Code), arising fr om purchases of goods, materials, or services by the bidder for sale to the purchasing body pursuant to the bid. Such assignment shall be made and become effective at the time the purchasing body tenders final payment to the bidder.

28.1.3 Section 4553 of the Government Code states:

If an awarding body or public purchasing body receives, either through judgment or settlement, a monetary recovery for a cause of action assigned under this chapter, the assignor shall be entitled to receive reimbursement for actual legal costs incurred and may, upon demand, recover from the public body any portion of the recovery, including treble damages, attributable to overcharges that were paid by the assignor but were not paid by the public body as part of the bid price, less th e expenses incurred in obtaining that portion of the recovery.

28.1.4 Section 4554 of the Government Code states:

G520

Upon demand in writing by the assignor, the assignee shall, within one year from such demand, reassign the cau (t)-8.6 (y)-10.5 (e) (y)-10.5 (e722(t)2.4 ((f)-5. (e)1 (e))0.5 ((y 4.8 (.494 -1)-8.5 ()-8

28.4 Shipments

Contractor is responsible for any or all damage or lo ss to shipments until delivered and accepted on Site, as indicated in the Contract Documents. There must be no charge for containers, packing, unpnn04 Tom g1 5045 Tw 5 578 e 0 Tc 1 2 Tj 0 0 4 (T) j 8 0 0 4 0 5 w 3 0 3 4 9 0 5 T [(a) 3 4 9 (np) 2 [5 0 (5 (np)

disruption to school operations and any use of school facilities by the public up to, and including, rescheduling specific work activities, at no additional cost to District.

G. No Work during Student Testing. Contractor shall, at no additional cost to the District and at the District's request, coordinate its Work to not disturb District students including, without limitation, not performing any Work when students at the Site are taking State or Federally -required tests.

3. Badge Policy for Contractors

All Contractors doing work for the District will provide their workers with identification badges. These badges will be worn by all members of the Contractor's staff who are working in a District facility.

A. Badges must be filled out in full and contain the following information:

3.1.1 Name of Contractor

3.1.2 Name of Employee

3.1.3 Contractor's address and phone number

B. Badges are to be worn when the Contractor or his/her employees are on site and must be visible at all times. Contractors must inform their employees that they are required to allow District employees, the Low

aided design and drafting ("CADD") files, PDF format , plus one set of As-Built Drawings in Hard Copy.

B. Contractor shall submit Record Drawings pursuant to the Contract Documents consisting of one set of computer-aided design and drafting ("CADD") files, PDF format, plus one set of Record Drawings in Hard Copy.

6. Construction Manager

The District will use a Construction Manager on the Project that is the subject of this Contract. 6.

Contract Price or Contract Co6d1 ( )Tj -0.005 Tc 0dhUrac

b. Contractor shall develop and implement a system acceptable to District to track hazardous waste from the Site to d isposal, including appropriate "Hazardous Waste Manifests" on the EPA form, so that District may track the volume of waste it put in each landfill and receive from each landfill a certificate of receipt.

c. Contractor shall provide District with the name and address of each waste disposal

d isporms

b. In the case of any permits or notices held in District's name or of necessity to be made in District's name, District shall cooperate with Contractor in securing the permit or giving the notice, but the Contractor shall prepare for District review and execution upon approval, all necessary applications, notices, and other materials.

8. Indemnification

To the fullest extent permitted by law, the indemnities and limitations of liability expressed throughout the Contract Documents apply with equal force and effect to any claims or liabilities imposed or existing by virtue of the removal, abatement, and disposal of hazardous waste. This includes, but is not limited to, liabilities connected to the selection and use of a waste disposal facility, a waste transporter, personal injury, property damage, loss of use of property, damage to the environment or natural resources, or "disposal" and "release" of materials associated with the Work (as defined in 42 U.S.C. § 960l et seq .).

9. Termination

District shall have an absolute right to terminate for default immediately without notice and without an opportunity to cure should Contractor knowingly or recklessly commit a material breach of the terms of the Contract Documents, or any applicable law, on any matter involving the exposure of persons or property to hazardous waste. However, if the breach of contract exposing persons or property to hazardous waste is due solely to an ordinary, unintentional, and non-reckless failure to exercise reasonable care, then the procedures for termination for cause shall apply without modification.

END OF DOCUMENT

SACRAMENTO

section of the Specifications the description of the actual product(s) installed, including the following:

(1) Manufacturer's name and product model and number.

(2) Product substitutions or alternates utilized.

(3) Changes made by Addenda and Change Orders and written

1.09 PROTECTION OF EXISTING STRUCTURES AND UTILITIES

A. The Drawings show above-grade and below-grade structures, utility lines, and other installations that are known or believed to exist in the area of the Work. Contractor shall locate these existing installations before proceeding with excavation and other operations that could damage same; maintain them in service, where appropriate; and repair damage to them caused by the performance of the Work. Should damage occur to these existing installations, the costs of repair shall be at the Contractor's expense and made to the District's satisfaction.

B. Contractor shall be alert to the possibility of the existence of additional structures and utilities. If Contractor encounters additional structures and utilities, Contractor will immediately report to the District for disposition of same as indicated in the General Conditions.

1.10 UTILITY SHUTDOWNS AND INTERRUPTIONS

A. Contractor shall give the District a minimum of three (3) days written notice in advance of any need to shut off existing utility services or to effect

DOCUMENT 01 22 00

UNIT PRICING

PART 1 – ALTERNATES

1.01 RELATED DOCUMENTS AND PROVISIONS

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions;

B. Special Conditions;

C. Bid Form and Proposal;

D. Instruction to Bidders.

1.02 DESCRIPTION

The items of work indicated below propose modifications to, substitutions for, additions to and/or deletions from the various parts of the Work specified in other Sections of the Specifications. The acceptance or rejection of any of the alternates is strictly at the option of the District subject to District's acceptance of Contractor's stated prices contained in this Proposal.

1.03 GENERAL

Where an item is omitted, or scope of Work is decreased, all Work pertaining to the item whether specifically stated or not, shall be omitted and where an item is added or modified or where scope of Work is increased, all Work pertaining to that required to render same ready for use on the Project in

Drawings and Specifications, must be referred to for the complete scope of Work.

PART 2 - UNIT PRICING (NOT USED)

2.01 GENERAL

Contractor shall completely state all required figures based on Unit 38.5 (u)-10d ortait 38.5 (u)-10d i 38.5 (u)-10or

DOCUMENT 01 25 13

PRODUCT OPTIONS AND SUBSTITUTIONS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. Instructions to Bidders;

B. General Conditions, including, without limitation, Substitutions For Specified Items; and

C. Special Conditions.

1.02 SUBSTITUTIONS OF MATERIALS AND EQUIPMENT

A. Catalog numbers and specific brands or trade names followed by the designation "or equal" are used in conjunction with material and equipment required by the Specifications to establish the standards of quality, utility, and appearance required. Substitutions which are equal in quality, utility, and

DOCUMENT 01 29 00

APPLICATION FOR PAYMENT AND
CONDITIONAL AND UNCONDITIONAL WAIVER AND RELEASE FORMS

CONTRACTOR SHALL COMPLY WITH ALL PROVISIONS IN THE GENERAL CONDITIONS RELATED TO APPLICATIONS FOR PAYMENT AND/OR PAYMENTS.

CONDITIONAL WAIVER AND RELEASE
ON PROGRESS PAYMENT
(CIVIL CODE SECTION 8132)

NOTICE: THIS DOCUMENT WAIVES THE CLAIMANT'S LIEN, STOP PAYMENT NOTICE, AND PAYMENT BOND RIGHTS EFFECTIVE ON RECEIPT OF PAYMENT. A PERSON SHOULD NOT RELY ON THIS DOCUMENT UNLESS SATISFIED THAT2.4941t EMC -1.229 Td(O)6.9 (C/(N)4 (T)4.6 ( )-11.5 (H)-5 ASN

(4) Contract rights, including (A) a right based on rescission, abandonment, or breach of contract, and (B) the right to recover compensation for work not compensated by the payment.

Claimant's Signature: _____

Claimant's Title: _____

Date of Signature: _____

UNCONDITIONAL WAIVER AND RELEASE
ON P ROGRESS PAYMENT
(CIVIL CODE SECTION 8134)

NOTICE TO CLAIMANT : THIS DOCUMENT WAIVES AND RELEASES LIEN, STOP PAYMENT NOTICE, AND PAYMENT BOND RIGHTS UNCONDITIONALLY AND STATES THAT YOU HAVE BEEN PAID FOR GIVING UP THOSE RIGHTS. THIS DOCUMENT IS ENFORCEABLE AGAINST YOU IF YOU SIGN IT, EVEN IF YOU HAVE NOT BEEN PAID. IF YOU HAVE NOT BEEN PAID, USE A CONDITIONAL WAIVER AND RELEASE FORM.

Name of Clai0 Tw 2 (o)6.6

Na0 T7.9 (e)0.6 (3)-11 [illegible]

CONDITIONAL WAIVER AND RELEASE
ON FINAL PAYMENT
(CIVIL CODE SECTION 8136)

NOTICE: THIS DOCUMENT WAIVES THE CLAIMANT'S LIEN, STOP PAYMENT NOTICE, AND PAYMENT BOND RIGHTS EFFECTIVE ON RECEIPT OF PAYMENT. A PERSON SHOULD NOT RELY ON THIS DOCUMENT UNLESS SATISFIED THAT THE CLAIMANT HAS RECEIVED PAYMENT.

Name of Claimant: _____

Name of Customer: _____

Job Location: _____

Owner: _____

Conditional Waiver and Release

This document waives and releases lien, stop payment notice, and payment bond rights the claimant has for labor and service provided, and equipment and material delivered, to the customer on this job. Rights based upon labor or service provided, or equipment or material delivered, pursuant to a written change order that has been fully executed by the parties prior to the date that this document is signed by the claimant, are waived and released by this document, unless listed as an Exception below. This document is effective

UNCONDITIONAL WAIVER AND RELEASE
ON FINAL PAYMENT
(CIVIL CODE SECTION 8138)

NOTICE TO CLAIMANT : THIS DOCUMENT WAIVES AND RELEASES LIEN, STOP PAYMENT NOTICE, AND PAYMENT BOND RIGHTS UNCONDITIONALLY AND STATES THAT YOU HAVE BEEN PAID FOR GIVING UP THOSE RIGHTS. THIS DOCUMENT IS ENFORCEABLE AGAINST YOU IF YOU SIGN IT, EVEN IF YOU HAVE NOT BEEN PAID. IF YOU HAVE NOT BEEN PAID, USE A CONDITIONAL WAIVER AND RELEASE FORM.

Name of Claimant: _____

Name of Customer: _____

Job Location: _____

Owner: _____

Unconditional Waiver and Release

This document waives and releases lien, stop payment notice, and payment bond rights the claimant has for all labor and service provided, and equipment and material delivered, to the customer on this job. Rights based upon labor or service provided, or equipment or material delivered, pursuant to a written change order that has been fully executed by the parties prior to the date that this document is signed by the claimant, are waived and released by this document, unless listed as an Exception below. The claimant has been paid in full.

Exceptions

This document does not affect any of the following: _____

Disputed claims for extras in the amount of: $ _____

Claimant's Signature: _____

Claimant's Title: _____

Date of Signature: _____

DOCUMENT 01 31 19

PROJECT MEETINGS

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:PROISIO

C. Milestone Schedule:

Preliminary Construction Schedule

1.04 QUALIFICATIONS

A. Contractor shall employ experienced scheduling personnel p2-0 0 9.96 108 273868 Tm (A.)Tj /TT2 qualifoi r20.6 (e]TJ 4Td ( )Tj 0.928 0 T

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter

E. Failure of Progress Schedule to include any element of the Work, or any inaccuracy in Progress Schedule, will not relieve Contractor from responsibility for accomplishing the Work in accordance with the Contract. District's acceptance of sch edule shall be for its use in monitoring and evaluating job progress, payment requests, and time extension requests and shall not, in any manner, impose a duty of care upon District, or act to relieve Contractor of its responsibility for means and methods of construction.

F. Software: Use District Preferred Project Planning Software. Such software shall be compatible with Windows operating system. Contractor shall transmit contract file to District on compact disk at times requested by District.

G. Transmit each item under the form approved by District.

(1) Identify Project with District Contract number and name of Contractor.

(2) Provide space for Contractor's approval stamp and District's review stamps.

(3) Submittals received from sources other than Contractor will be returned to the Contractor without District's review.

1.06 INITIAL CPM SCHEDULE

A. Initial CPM Schedule submitted for review at the pre-construction conference shall serve as Contractor's schedule until Project Schedule is submitted.

any missing information

(a) Include time for fabrication and delivery of manufactured products for the Work.

(b) Show dependencies between procurement and construction.

(9) Activity description; what Work is to be accomplished and where.

(10) The total estimated number of man-hours for performing each activity shall be stated.

(d) Furnish schedule for Contractor/Subcontractor CPM schedule meetings which shall be held prior to submission of Original CPM schedule to District. District shall be permitted to attend 3.5Td j 0.4istid icicn

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

revised sequence of work. The Contractor shall provide the written narrative and schedule diagram for revisi ons two (2) working days in advance of the monthly schedule update meeting.

C. Schedule revisions shall not be incorporated into any schedule update until the revisions have been reviewed by District. District may request further information and justificatio n for schedule revisions and Contractor shall, within three (3) days, provide District with a complete written narrative response to District's request.

D. If the Contractor's revision is still not accepted by District, and the Contractor disagrees with District's position, the Contractor has seven (7) calendar days from receipt of District's letter rejecting the revision to provide a written narrative providing full justification and explanation for the revision. The Contractor's failure to respond in writing within seven (7) calendar days of District's written rejection of a schedule revision shall be contractually interpreted as acceptance of District's position, and the Contractor waives its rights to subsequently dispute or file a claim regarding District's position.

E. At District's discretion, the Contractor can be required to provide Subcontractor certifications of performance regarding proposed schedule revisions affecting said Subcontractors.

EMC /LBody <</MCID 42 >>BDC -

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter

B. Samples, Shop Drawings, Product Data, and other items as specified, in accordance with the following requirements:

(1) Contractor shall submit all Shop Drawings, Product Data, and Samples to the District, the Low Voltage Consultant, the Project Inspector, and the Construction Manager.

(2) Contractor shall comply with all time frames herein and in the General Conditions and, in any case, shall submit required information in sufficient time to permit proper consideration and action befor e ordering any materials or items represented by such Shop Drawings, Product Data, and/or Samples.

(3) Contractor shall allow sufficient time so that no delay occurs due to required lead time in ordering or delivery of any item to the Site. Contractor shall be responsible for any delay in progress of Work due to its failure to observe these requirements.

(4) Time for completion of Work shall not be extended on account of Contractor's failure to promptly submit Shop Drawings, Product Data, and/or Samples.

(5) Reference numbers on Shop Drawings shall have Low Voltage Consultant ural and/or Engineering Contract Drawings reference numbers for details, sections, and “cuts” shown on Shop Dy These reference numbers shall be in addition to any numbering system t hat Contractor chooses to use or has adopted as standard.

(6) When the magnitude or complexity of submittal material prevents a complete review within the stated time frame, Contractor shalime

C. Submittal Schedule:

(1) Contractor shall prepare its proposed submittal schedule that is coordinated with the proposed construction schedule and submit both to the District within ten (10) days after the date of the Notice to Proceed. Contractor's proposed schedules shall become the Project Construction Schedule and the Project Submittal Schedule after each is approved by the District.

(2) Contractor is responsible for all lost time should the initial submittal be rejected, marked "revise and resubmit", etc.

(3) All Submittals shall be forwarded to the District by the date indicated on the approved Submittal Schedule, unless an earlier date is necessary to maintain the Construction Sched ule, in which case those Submittals shall be forwarded to the District so as not to delay the Construction Schedule.

(4) Contractor may be assessed $100 a day for each day it is late in submitting a shop drawing or sample. No extensions of time will be grante d to Trade Contractor or any Subcontractor because of its failure to have shop drawings and samples submitted in accordance with the Schedule.

1.03 SHOP DRAWINGS:

A. Contractor shall submit one reproducible transparency and six (6) opaque reproductions. The District will review and return the reproducible copy and one (1) opaque reproduction to Contractor.

B. Before commencing installation of any Work, the Contractor shall submit and receive approval of all drawings, descriptive data, and material list(s) as required to accomplish Work.

C.Rrevi-202.5 (u)-1.7 (f217 Td s)-2.1 S-14.1 (i)-20.2 (op(d)-8.6 s)-2.1 D (d)0.5rahi-20d [(re)0.6 (n)-20.2 (g)311.2 (20.1

Documents and not indicated on Shop Drawings. The District's and/or Low Voltage Consultant's review of Shop Drawings is not to be construed as approving departures from Contract Documents.

G. Review of Shop Drawings and Schedules does not relieve Contractor from responsibility for any aspect of those Drawings or Schedules that is a violation of Code, Law, or Regulation.

D. Equipment submittals shall be complete and include space requirements, weight, electrical and mechanical requirements, performance data, and supplemental information that may be requested.

E. Imported Materials Certification must be submitted at least ten (10) days before material is delivered.

1.05 SAMPLES:

A. Contractor shall submit for approval Samples as required and within the time frame in the Contract Documents. Materials such as concrete, mortar, etc., which require on-site testing will be obtained from Project Site.

B. [illegible]

J. Samples which are rejected must be resubmitted promptly after notification of rejection and be marked "Resubmitted Sample" in addition to other information required.

K. Field Samples and Mock-Ups are to be removed by Contractor at District's direction:

(1) Size: As Specified.

(2) Furnish catalog numbers and similar data, as requested.

1.06 REVIEW AND RESUBMISSION REQUIREMENTS:

A. The District will arrange for review of Sample(s), Shop Drawing(s), Product Data, and other submittal(s) by [illegible]

H. Neither the review nor the lack of review of any Sample(s), Shop Drawing(s),

DOCUMENT 01 35 13.23

SITE STANDARDS

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including without limitation, Site Access, Conditions, and Regulations;

B. Special Conditions;

C. Drug-Free Workplace Certification;

D. Tobacco-Free Environment Certification;

E. Criminal Background Investigation/Fingerprinting Certification;

F. Temporary Facilities and Controls.

1.02 REQUIREMENTS OF THE DISTRICT:

A. Drug-Free Schools and Safety Requirements:

(1) All school sites and other District Facilities have been declared “Drug-Free Zones.” No drugs, alcohol and/or smoking are allowed at any time in any buildings and/or grounds on DistrictnFn;

C. Disturbing the Peace (Noise and Lighting):

(1) Contractor shall observe the noise ordinance of the Site at all times including, without limitation, all applicable local, city, and/or state laws, ordinances, and/or regulations regarding noise and allowable noise levels.

(2) The use of radios, etc., shall be controlled to keep all sound at a level that cannot be heard beyond the immediate area of use. District reserves the right to prohibit the use of radios at the Site, except for mobile phones or other handheld communication radios.

(3) If portable lights are used after dark, all light must be located so as not to direct light into neighboring property.

D. Traffic:

(1) Driving on the Premises shall be limited to periods when students and public are not present. If driving or deliveries must be made during the school hours, two (2) or more ground guides shall lead the vehicle across t he area of travel. In no case shall driving take place across playgrounds or other pedestrian paths during recess, lunch, and/or class period changes. The speed limit on-the Premises shall be five (5) miles per hour (maximum) or less if conditions require.

(2) All paths of travel for delive t h e r i e s m u s t b e 8.6l (e)0.ss

DOCUMENT 01 41

SACRAMENTO CITY USD REGULATORY
Joseph Bonnheim ES Telecenter
Upgrades

DOCUMENT 01 42 16

DEFINITIONS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions including without limitation, Definitions;

B. Special Conditions.

1.02 QUALITY ASSURANCE

A. For products or workmanship specified by association, trade, or Federal Standards, Contractor shall comply with requirements of the standard, except when more rigid requirements are specified in the Contract Documents, or are required by applicable codes.

B. Contractor shall conform to current reference standard publication date in effect on the date of bid opening.

C. Contractor shall obtain copies of standards unless specifically required not to by the Contract Documents.

D. Contractor shall maintain a copy of all standard s at jobsite during submittals, planning, and progress of the specific Work, until final completion, unless specifically required not to by the Contract Documents.

E. Should specified reference standards conflict with Contract Documents, Contractor shall request clarification from the District and/or the Low Voltage Consultant before proceeding.

F. The contractual relationship of the parties to the Contract shall not be altered from the contractual relationship as indicated in the Contract Documents by menti on or inference otherwise in any referenced document.

G. Governing Codes shall be as shown in the Contract Documents including, without limitation, the Specifications.

END OF DOCUMENT

DOCUMENT 01 42 19

REFERENCES

PART 1 - 7ES

ADC	Air Duct Council 1901 N. Roselle Road, Suite 800 Schaumburg, IL 60195 www.flexibleduct.org	847/706 - 6750
AF&PA	American Forest and Paper Association 1101 K Street, NW, Suite 700 Washington, DC 20005 www.afandpa.org	202/463 - 2700
AGA	American Gas Association 400 North Capitol Street, NW, Suite 450 Washington, DC 20001 www.aga.org	202/824 - 7000

ALI	Associated Laboratories, Inc. P.O. Box 152837 Dallas, TX 75315 www.assoc-labs.com	214/565-0593

EPA	Environmental Protection Agency Ariel Rios Building 1200

IAPMO	International Association of Plumbing and Mechanical Officials (formerly the Western Plumbing Officials Association) 4755 E. Philadelphia St. Ontario, CA 91761 www.iapmo.org	909/472 -4100
ICC	International Code Council 500 New Jersey Avenue, NW, 6th Floor Washington, DC 20001 www.iccsafe.org	888/422 -7233
IEEE	Institute of Electrical and Electronics Engineers	

SACRAMENTO

NGA (formerly GANA)	National Glass Association (merged

SDI	Steel Door Institute 30200 Detroit Road Westlake, OH 44145 www.steeldoor.org	440/899 -0010
SJI	Steel Joist Institute 140 West Evans Street, Suite 203 Florence, SC 29501 http://steeljoist.org	843/407 -4091
SMA	Stucco Manufacturers Association 5753 E Santa Ana Cyn Rd, #G -156 Anaheim, CA 92807 www.stuccomfgassoc.com	714/473 -9579
SMACNA	Sheet Metal and Air Conditioning Contractors' National Association 4201 Lafayette Center Drive Chantilly, VA 20151- 1219 www.smacna.org	703/803 -2980
SPI	SPI: The Plastics Industry Trade Association, Inc. 1425 K St. NW, Suite 500 Washington, DC 20005 www.plasticsindustry.org	202/974 -5200
TCA	The Tile Council of North America 100 Clemson Research Blvd. Anderson, SC 29625 www.tcnatile.com	864/646 -8453
TPI	Truss Plate Institute 2670 Crain Highway, Suite 203 Waldorf, MD 20601 www.tpinst.org	240/587 -5582
TPI	Turfgrass Producers International 444 E. Roosevelt Road #346 Lombard, IL 60148 www.turfgrasssod.org	800/405 -8873 847/649 -5555
TCIA	Tree Care Industry Association (formerly the National Arborist Association) 670 N Commercial Street, Suite 201 Manchester, NH 03101 www.tcia.org	603/314 -5380 800/733 -2622

PART 3 - EXECUTION

3.01 WORKMANSHIP

A. Where not more specifically described in any other Contract Documents, workmanship shall conform to methods and operations of best standards and accepted practices of trade or trades involved and shall include items of fabrication, construction, or install ation regularly furnished or required for completion (including finish and for successful operation, as intended).

B. Work shall be executed by tradespersons skilled in their respective lines of Work. When completed, parts shall have been durably and substantially built and present a neat appearance.

3.02 COORDINATION

A. Contractor shall coordinate installation of Work so as to not interfere with installation of others. Adjustment or rework because of Contractor's failure to coordinate will be at no additional cost to District.

B. Contractor shall examine in-place work for readiness, completeness, fitness to be concealed or to receive other work, and in compliance with Contract Documents. Concealing or covering Work constitutes acceptance of additional cost which will result should in-place Work be found unsuitable for receiving

3.05 MANUFACTURER'S RECOMMENDATIONS

All installations shall be in accordance with manufacturer's published recommendations and specific written directions of manufacturer's representative. Should Contract Documents differ from recommendations of manufacturer or directions of his representative, Contractor shall analyze differences, make recommendations to the District and the Low Voltage Consultant in writing, and shall not proceed until interpretation or clarification has been issued by the District and/or the Low Voltage Consultant .

END OF DOCUMENT

DOCUMENT 01 45 00

QUALITY CONTROL

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including, without limitation, Inspector, Inspections and Tests, Uncovering of Work and Non - conforming of Work and Correction of Work;

B. Special Conditions.

1.02 RELAonLA 45

(3) The Project Inspector shall observe and monitor all testing and inspection activities required.

The Contractor shall conform with all applicable laws as indicated in the Contract Documents, including, without limitation, to CCR, Part 1, Title 24, Section 4 -343. The Contractor shall supervise and direct the Work and maintain a competent superintendent on the job who is authorized to act in all matters pertaining to the Work. The Contractor's superintendent shall also inspect all materials, as they arrive, for com.6 (i)-2.2 (r)97.9 (M)-6.7P(3)0.5 (43)0.5 (.)]TJ 0 Tc 0 Tw 2.277 0 Td ( )Tj 0.004 Tc -0.006 Tw -41.036 -

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter

Testing agency shall test concrete used in the work per the following paragraphs:

(1) Compressive Strength:

(a) Minimum number of tests required: One (1) set of three (3) cylinders for each 100 cubic yards (Sec. 2604(h) 01) of concrete or major fraction thereof, placed in one (1) day. See Title 24, Section 2605(g).

(b) Two cylinders of each set shall be tested at twenty - eight (28) days. One (1) cylinder shall be held in reserve and tested only when directed by the

DOCUMENT 01 50 00

TEMPORARY FACILITIES AND CONTROLS

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions;

B. Special Conditions;

C. Site Standards; and

D. Construction Waste Management and Disposal.

1.02 TEMPORARY UTILITIES:

A. Electric Power and Lighting:

(1) Contractor will pay for power during the course of the Work. To the extent power is available in the building(s) or on the Site, Contractor may use the District's existing utilities by making prearranged payments to the District for the utilities used by Contractor and all Subcontractors. Contractor shall be responsible for providing temporary facilities required to deliver that power service from its existing location in the building(s) or on the Site to point of intended use.

(2) Contractor shall verify characteristics of

minimum conditions for the installation and curing of materials, and to protect materials and finishes from damage due to improper temperature and humidity conditions. Portable heaters shall be standard units complete with controls.

(2) Contractor shall provide forced ventilation and dehumidification, as required, of enclosed areas for proper installation and curing of materials, to disperse humidity, and to prevent hazardous accumulations of dust, fumes, vapors, and gases.

(3) Contractor shall pay the costs of installation, maintenance, operation, and removal of temporary heat and ventilation, including costs for fuel consumed, required for the performance of the Work.

C. Water:

(1) Co

SACRAMENTO

B. None of the District's tools and equipment shall be used by Contractor for the performance of the Work.

1.04 BARRIERS AND ENCLOSURES:

A. Contractor shall obtain the District's written permission for locations and types of temporary barriers and enclosures, including fire-rated materials proposed for use, prior to their installation.

B. Contractor shall provide and maintain temporary enclosures to prevent public entry and to protect persons using other buildings and portions of the Site and/or Premises, the public, and workers. Contractor shall also protect the Work and existing facilities from the elements, and adjacent construction and improvements, persons, and trees and plants from damage and injury from demolition and construction operations.

C. Contractor shall provide site access to existing facilities for persons using other buildings and portions of the Site, the public, and for deliveries and other services and activities(p)0.5 (r)9.3 (o18.5 (c)-r(a)0.6 (n)s(o)8.6 (m)1.1 (ess)-5.2 (7 (0.003 Tw 0.3379

(a) Where trenching for utilities is required within drip lines, tunneling under and around roots shall be by hand digging and shall be approved by the District. Main lateral roots and taproots shall not be cut. All roots 2 inches in diameter and larger shall be tunneled under and heavily wrapped with wet burlap so as to prevent scarring or excessive drying. Smaller roots that interfere with installation of new work may be cut with prior approval by the District. Roots must first be cut with a Vermeer, or equivalent, root cutter prior to any trenching.

(b) Where excavation for new construction is required within drip line of trees, hand excavation shall be employed to minimize damage to root system. Roots shall be relocated in backfill areas

1.05 SECURITY:

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

SACRAMENTO CITY USD TEMPORARY
Joseph Bonnheim ES Telecenter
Upgrades

1.04 PERFORMANCE REQUIREMENTS:

A. General: Develop waste management plan that results in end-of Project rates for salvage/recycling of sixty-five percent (65%) by weight (or by volume, but not a combination) of total waste generated by the Work.

1.05 SUBMITTALS:

A. Waste Management Plan: Submit waste management plan within 30 days of date established for commencement of the Work.

B. Waste Reduction Progress Reports: Concurrent with each Application for Payment, submit copies of report. Include the following information:

(1) Material category.

(2) Generation point of waste.

(3) Total quantity of waste in tons or cubic yards.

(4) Quantity of waste salvaged, both estimated and actual in tons or cubic yards.

(5) Quantity of waste recycled, both estimated and actual in tons or cubic yards.

(6) Total quantity of waste recovered (salvaged plus recycled) in tons or cubic yards.

(7) Total quantity of waste recovered (salvaged plus recycled) as a percentage of total waste.

C. Waste Reduction Calculations: Before request for final payment, submit copies of calculated end-of-Project rates for salvage, recycling, and disposal as a percentage of total waste generated by the Work(d)]TJ ta-2.4 ( )-(t)-8.6 (h.6 (a)24 ( )0TJ)0.6 (t)-7.2-2.1

H. Qualificat ion Data: For Waste Management Coordinator.

I. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

J. Submittal procedures and quantities are specified in

(1) Salvaged Materials for Reuse: For materials that will be salvaged and reused in this Project, describe methods for preparing salvaged materials before incorporation into the Work.

(2) Salvaged Materials for Sale: For materials that will be sold to individuals and organizations, include list of

(3) Pallets: As much as possible, require deliveries using pallets to remove pallets from Project Site. For pallets that remain on Site, break down pallets into component wood pieces and comply with requirements for recycling wood.

(4) Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

E. Site-Clearing Wastes: Chip brush, branches, and trees on site.

F. Wood Materials:

(1) Clean Cut-Offs of Lumber: Grind or chip into small pieces.

(2) Clean Sawdust: Bag sawdust that does not contain painted or treated wood.

G. Gypsum Board: Stack large clean pieces on wood pallets and store in a dry location.

(1) Clean Gypsum Board: Grind scraps of clean gypsum board using small mobile chipper or hammer mill. Screen out paper after grinding.

3.03 DISPOSAL OF WASTE:

A. General: Except for items or materials to be salvaged, recycled, or otherwise reused, remove waste materials from Project Site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

(1) Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on site.

(2) Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

C. Disposal: Transport waste materials off District property and legally dispose of them.

END OF DOCUMENT

DOCUMENT 01 52 13

FIELD OFFICES

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions;

B. Special Conditions; and

C. Temporary Facilities and Controls.

1.02 SECTION INCLUDES:

A. Requirements for Field Offices and Field Office Trailers.

1.03 SUMMARY:

A. General: Contractor shall provide District's Field Office Trailer and contents, for District's use exclusively, during the term of the Contract.

B. Property: Trailer, furniture, furnishings, equipment, and the like, supplied by

C. Equipment Data: Two (2) copies of manufacturer data for each type of equipment, if directed by District.

D. Furniture and Furnishings Data: Two (2) copies of manufacturer data for each type of equipment, if directed by District.

E. Plans: One (1) reproducible copy of appropriately scaled plans of trailer layout. Plans shall include, but not be limited to: lighting; furniture; equipment; telephone and electrical outlets; and the like.

F. Product Samples: One (1) complete and entd

D. Coach Insignia: Trailer shall display California Commercial Coach Insignia; such insignia shall be deemed to show that the trailer is in accordance with the Construction and Fire Safety requirements of CCR.

PART 2 – PRODUCTS

2.01 FIELD OFFICE TRAILER

A. General: Provide entire Field Office Trailer of type, function, operation, capacity, size, complete with controls, safety devices, accessories, and the like, for proper and durable installation. Partitions, walls, ceiling, and other interior and exterior surfaces shall be appropriately finished, including, but not limited to, trim, painting, wall base, f loor coo

SACRAMENTO

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

and the like, as required for a complete, structurally rigid, stable, sound, and appropriately finished installation, in accordance with manufacturer's published instructions, and as indicated. The more restrict ive and higher quality requirement shall govern. Moving parts shall be properly secured, without binding, looseness, noise, and the like.

B. Installation: Install in accordance with 25 CCR 3.2.3 and as directed by District; jack up trailer and level both ways; mount on proper concrete piers with all load off wheels; provide If ufacture2 -1T6 Tw e 0 aiufa w -0.005 Tc 0.005 Tw 0.4 -0.005 T792 (o0

DOCUMENT 01 64 00

OWNER -FURNISHED PRODUCTS

SACRAMENTO

7) Install materials and equipment in accordance with manufacturer's recommendations, instructions, and Shop Drawings, supply labor and material required, and make mechanical, plumbing, and electrical connections required to operate equipment.

8) Be certified by equipment manufacturer for installation of the specific equipment supplied by the Owner.

9) Provide anchorage and/or bracing as required for seismic restraint per Title 24, UBC Standard 27-11 and all other applicable codes.

10) Provide the contract-required warranty and guarantee for all work, materials and equipment, and installation upon its completion and acceptance by the District. Guarantee includes all costs associated with the removal, shipping to and from the Site, and re-installation of any equipment found to be defective.

C. Compatibility with Space and Service

SECTION 01 66 00

PRODUCT DELIVERY, STORAGE AND HANDLING

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. Generalewa.00 Tc -0.002C8 Tm8 (s)-1.1 (i)-1o1w4 [(re)-19.2 (s)-1.1 (i)-19.1 (-)6 (E)-2.8 (RY)3.1 (s)51TJ 0 T

DOCUMENT 01 71 23

FIELD ENGINEERING

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISI1.4 (V)-12b>>BD.9 :S

1.05 RECORDS:

Contractor shall maintain a complete, accurate( )Tj ET EMC BT 1 0 0 1 56.73 Tc 0 Tw 3 0 (.0 9.48

SACRAMENTO CITY USD
Joseph Bonnheim ES Telecenter
Upgrades

DOCUMENT 01 76 00

ALTERATION PROJECT PROCEDURES

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including, without limitation, Integration of Work, Purchase of Materials and Equipment, Uncovering of Work and Non-conforming Work and Correction of Work and Trenches;

B. Special Conditions.

PART 2 - PRODUCTS

2.01 PRODUCTS FOR PATCHING AND EXTENDING WORK:

A. New Materials: As specified in the Contract Documents including, without limitation, in the Specifications, Contractor shall match existing products, conditions, and work for patching and extending work.

B. Type and Quality of Existing Products: Contractor shall determine by inspection, by testing products where necessary, by referring to existing conditions and to the Work as a standard.

PART 3 - EXECUTION

3.01 EXAMINATION:

A. Contractor shall verify that demolition is complete and that areas are ready for installation of new Work.

B. By beginning restoration Work, Contractor acknowledges ( )T74g1 0 .313 0 T ( )T2r6N5 Td [(Wo)-8.4 (r

C. Contractor shall remove debris and abandoned items from all areas of the Site and from concealed spaces.

D. Contractor shall prepare surface and remove surface finishes to provide for proper installation of new Work and finishes.

E. Contractor shall close openings in exterior surfaces to protect existing work from weather and extremes of temperature and humidity. Contractor shall insulate ductwork and piping to prevent condensation in exposed areas. Contractor shall insulate building cavities for thermal and/or acoustical protection, as detailed.

3.03 INSTALLATION:

A. Contractor shall coordinate Work of all alternations and renovations to expedite completion and to acc ommodate District occupancy.

B. Designated Areas and Finishes: Contractor shall complete all installations in all respects, including operational, mechanical work and electrical work.

C. Contractor shall remove, cut, and patch Work in a manner to minimize dama ge and to provide a means of restoring Products and finishes to original or specified condition.

D. Contractor shall refinish visible existing surfaces to remain in renovated rooms and spaces, to specified condition for each material, with a neat and square or straight transition to adjacent finishes.

E. Contractor shall install products as specified in the Contract Documents, including witD 66 >>43.5 ( )7 (n)-1.5 ( )0.6 (to)8.6 ( )0.6 (-da0 TdTc 0 ( )0.6im)2t nd.

DOCUMENT 01 77 00

CONTRACT CLOSEOUT AND FINAL CLEANING

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including, without limitation, Completion of Work;

B. Special Conditions;

C. Temporary Facilities and Controls.

1.02 CLOSEOUT PROCEDURES

Contractor shall comply with all closeout provisions as indicated in the General Conditi ( )Tj 0.003 T(ro)-1:e

1.05 RECORD DOCUMENTS AND SHOP DRAWINGS

A. Contractor shall legibly mark each item to record actual construction, including:

(1) Measured depths of foundation in relation to finish floor datum.

(2) Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permit surface improvements.

(3) Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.

(4) Field changes of dimension and detail.

(5) Details not on original Contract Drawings

(6) Changes made by modification(s).

(7) References to related Shop Drawings and modifications.

B. Contractor will provide one set of Record Drawings to District.

C. Contractor shall submit all required documents to District and/or Low Voltage Consultant prior to or with its final Application for Payment.

1.06 INSTRUCTION OF DISTRICT PERSONNEL

A. Before final inspection, at agreed upon times, Contractor shall instruct District's designated personnel in operation, adjustment, and maintenance of products, equipme nt, and systems.

B. For equipment requiring seasonal operation, Contractor shall perform instructions for other seasons within six months or by the change of season.

C. Contractor shall use operation and maintenance manuals as basis for instruction. Contractor shall review contents of manual with personnel in detail to explain all aspects of operation and maintenance.

D. Contractor shall prepare and insert additional data in Operation and Maintenance Manual when the need for such data becomes apparent during instruction.

E. Contractor shall review contents of manual with personnel in detail to explain all aspects of operation and maintenance.

1.07

B. Contractor shall provide District with all required Operation and Maintenance Data at one time. Partial or piecemeal submissions of Operation and Maintenance Data will not be accepted.

PART 2 – PRODUCTS Not Used.

PART 3 – EXECUTION Not Used.

END OF DOCUMENT

DOCUMENT 01 78 23

OPERATION AND MAINTENANCE DATA

PART 1 – GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including, without limitation, Completion of the Work;

B. Panelboard Circuit Directories: Contractor shall provide electrical service characteristics, controls, and communications.

C. Contractor shall include color coded wiring diagrams as installed.

D. Operating Procedures: Contractor shall include start-up, break-in, and routine normal operating instructions and sequences. Contractor shall include regulation, control, stopping, shut-down, and emergency instructions. Contractor shall include summer, winter, and any special operating instructions.

E. Maintenance Requirements: Contractor shall include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.

F. Contractor shall provide servicing and lubrication schedule, and list of lubricants required.

G. Contractor shall include manufacturer's printed operation and maintenance instructions.

H. Contractor shall include sequence of operation by controls manufacturer.

I. Contractor shall provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.

J. Contractor shall provide control diagrams by controls manufacturer as installed.

K. Contractor shall provide Contractor's coordination drawings, with color coded piping diagrams as installed.

L. Contractor shall provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.

M. Contractor shall provide list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.

N. Additional Requirements: Contractor shall include all additional requirements as specified in Specification(s).

O. Contractor shall provide a listing in Table of Contents for design data, with tabbed fly sheet and space for insertion of data.

1.07 SUBMITTAL:

A. Contractor shall submit to the District for review two (2) copies of preliminary draft or proposed formats and outlines of the contents of the Manual within thirty (30) days of Contractor’s start of Work.

B. For equipment, or component parts of equipment put into service during construction and to be operated by District, Contractor shall submit draft

content for that portion of the Manual within ten (10) days after acceptance of that equipment or component.

C. Contractor shall submit two (2) copies of a complete Manual in final form prior to final Application for Payment. Copy will be returned with Low Voltage Consultant /Engineer comments. Contractor must revise the content of the Manual as required by District prior to District's approval of Contractor 's final Application for Payment.

D. Contractor must submit two (2) copies as well as a PDF in searchable and tabbed format in Specification Section order of revised Manual in final

D. Contractor shall retain warranties until ttiil -6.4

DOCUMENT 01 78 39

RECORD DOCUMENTS

PART 1 - GENERAL

1.01 RELATED DOCUMENTS AND PROVISIONS:

All Contract Documents should be reviewed for applicable provisions related to the provisions in this document, including without limitation:

A. General Conditions, including, without limitation, Documents on Work;

B. Special Conditions.

PART 2 - RECORD DRAWINGS

2.01 GENERAL:

A. As indicated in the Contract Documents, the District will provide Contractor with one set of reproducible, full size original Contract Drawings.

B. Contractor shall maintain at each Project Site one set of marked-up plans and shall transfer all changes and information to those marked-up plans, as often as required in the Contract Documents, but in no case less than once each month. Contractor shall submit to the Project Inspector one set of reproducible Project Record Drawings ("As-Builts") showing all changes incorporated into the Work since the preceding monthly submittal. The As-Builts shall be available at the Project Site. The Contractor shall submit reproducible drawings at the conclusion of the Project following review of the blueline prints.

C. Label and date each Record Drawing "RECORD DOCUMENT" in legibly printed letters.

D. All deviations in construction, including but not limited to pipe and conduit locations and deviations caused by without limitation Change Orders, Construction Claim Directives, RFI's, and Addenda, shall be accurately and legibly recorded by Contractor.

E. Locations and changes shall be done by Contractor in a neat and legible manner and, where applicable, indicated by drawing a "cloud" around the changed or additional information.

2.02 RECORD DRAWING INFORMATION:

A. Contractor shall record the following information:

(1) Locations of Work buried under or outside each building, including, without limitation, all utilities, plumbing and electrical lines, and conduits.

(2) Actual numbering of each electrical circuit to match panel schedule.

(3) Locations of significant Work concealed inside each building whose general locations are changed from those shown on the Contract Drawings.

(4) Locations of all items, not necessarily concealed, which vary from the Contract Documents.

(5) Installed location of all cathodic protection anodes.

(6) Deviations from the sizes, locations, and other features of installations shown in the Contract Documents.

(7) Locations of underground work, points of connection with existing utilities, changes in direction, valves, manholes, catch basins, capped stubouts, and

5 (ou)-313 0 T9tume3Ysi (d)14 ( )NS(n.5 (m ( )Tj Bns)0 9.96 1850.001 Tc 0.001 Tw 05