



Sacramento City Unified School District

Business Services Contracts Office

5725 47th Avenue • Sacramento, CA 95824

(916) 643-2464

Gerardo Castillo, Chief Business Officer
Kimberly Teague, Contract Specialist

ADDENDUM NO. 2

Date: September 8, 2016

1. The existing site diagram "plan" sheet states "Remove & Replace Tennis Court Asphalt with

Overlay only

2. Section 02510, 1.03(E). Please clarify this will be a 1.5" overlay over existing and that contractor will not be held to this standard as this standard typically applies only to new
pavement within this extremely tight tolerance.

1.5" Overlay over existing

3. Section 02510, 2.01(A) Soil Sterilizer – please clarify this does not apply to this project.

Does not apply

4. Section 02510, 2.01(B) Aggregate Base – please clarify this does not apply to this project.

Does not apply

5. Section 02510, 2.01(F). Seal Coat – please clarify this does not apply to this project. (the court is getting specialty surface and that surface cannot be placed on seal)

Does not apply

to City Unified School District

6. Section 02510, 2.01(G). Header – please clarify this does not apply to this project. Further clarify that the existing is to remain.

Does not apply

7. Section 02510, 3.02(A). Subgrade – please clarify this does not apply to this project.

Does not apply

~~8. Section 02510, 3.02(A). Subgrade – please clarify this does not apply to this project.~~

~~1.5" Overlay over existing~~

~~9. Section 02510, 3.02(B). Subgrade – please clarify this does not apply to this project.~~

Does not apply

10. Section 02510, 3.03(C). Soil Sterilizer – please clarify this does not apply to this project.

Does not apply



amento City Unified School District

17. Section 02510, 3.03(F). Header Boards – please clarify this does not apply to this project.
Only applies to Header Board repair or replacement.
18. Section 02510, 3.04(A). Seal coat – please clarify this does not apply to this project.
~~As per Section 02525~~
19. Section 02510, 3.06(A). Patching and Repair – please clarify this does not apply to this project.
As per specification
20. Section 02510, 3.07. Testing - please clarify again that the District is expecting a 1.5” overlay over existing and contractor will not be held to correct existing drainage issues – ponding water.
1.5” Overlay over existing.
21. Please clarify what is to be done with net tie downs.
Adjust center net tie downs to receive 1.5” overlay.
22. Please clarify what is to be done with fence fabric that is waving and loose where it meets existing asphalt.
Adjust gates and fencing as needed.
23. Please clarify what gates needs to be adjusted and how? It looks like frames would actually have to be cut and reconstructed or new gates?
This is means and methods to receive 1.5” overlay.
24. Please clarify it will be OK to cut posts and then weld the post back together so we can access the court that has no vehicular gates.
All posts that are cut will need to be sleeved and welded.
25. How much cure time is required after overlay and before tennis court surfacing?
14 days
26. How many coats of paint are desired for line striping?
Two coats
27. Please confirm work will be 1.5” AC overlay with petromat fabric and not remove and
~~replace as shown per plans~~
Work will be 1.5” AC overlay with Petromat Fabric
28. Can you provide actual dimensions of the area to be overlaid?
Area of overlay is to encompass entire tennis court area within fencing (see attached).
29. Will existing color on pavement need to be removed prior to fabric & overlay?
No



30. If ponding occurs currently (prior to overlay) and we are placing an over 1.5" of A/C over the
~~1.5" A/C overlay on existing~~

31. Will soil sterilizer be required (see 2510-2.01A)?

See Question #10.

32. Will aggregate base be required (see 2510-2.01b)?

Not required

END OF ADDENDUM NO. 2

